

LOCATION OF UTILITY COMPANY
TRANSFORMER AND RELATED TRANSFORMER
PAD FOR BUILDING A, EAST HALF. INCLUDE
ALL REQUIREMENTS AS DIRECTED BY AEP
AND CIVIL ENGINEERING PLANS.
APPROXIMATE ROUTING OF ELECTRICAL
SERVICE SECONDARY SERVICE ENTRANCE
CONDUCTORS. REFER TO TRENCH SECTION
DETAIL "4" ON DRAWING #ES.02A.

APPROXIMATE ROUTING OF SERVICE
SECONDARY UNDERGROUND CONDUCTORS
FOR FIRE PUMP. REFER TO TRENCH
SECTION DETAIL "5" ON DRAWING #ES.02C.

APPROXIMATE ROUTING OF ELECTRICAL SERVICE
SECONDARY SERVICE ENTRANCE CONDUCTORS.
REFER TO TRENCH SECTION DETAIL "1" ON
DRAWING #ES.02A

LOCATION OF UTILITY COMPANY TRANSFORMER AND RELATED TRANSFORMER PAD FOR BUILDING A, WEST HALF. INCLUDE ALL REQUIREMENTS AS DIRECTED BY AEP AND CIVIL ENGINEERING PLANS.

**NOT FOR
CONSTRUCTION**

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC

whs
engineering

2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**

3455 W. Dublin Granville Rd,
Columbus OH, 43235


BUILDING A SITE ELECTRICAL PLAN

Date	Project Number
03.05.2026	24-065
Drawn by	Drawing Number
DJS	ES.01A
Checked by	
KDS	
Approved	
GSS	

Seal

**NOT FOR
CONSTRUCTION**

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BA
DESIGN DEVELOPMENT	03.05.26	BA

[illegible]

2012 West 25th Street, Suite 90
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**


**3455 W. Dublin Granville Rd,
Columbus OH, 43235**

BUILDING A SITE ELECTRICAL DETAILS

Date	Project Number
03.05.2026	24-065
Drawn by	Drawing Number
DJS	
Checked by	
KDS	ES.02/
Approved	
GSS	

1. PANELBOARDS RATED 240V AC OR LESS SHALL HAVE SHORT-CIRCUIT RATINGS AS SHOWN ON THE DRAWINGS OR AS HEREN SCHEDULED, BUT NOT LESS THAN 10,000 AMPERES, SYMMETRICAL.	2. PANELBOARDS RATED 480V AC OR LESS SHALL HAVE SHORT-CIRCUIT RATINGS AS SHOWN ON THE DRAWINGS OR AS HEREN SCHEDULED, BUT NOT LESS THAN 14,000 AMPERES, SYMMETRICAL.	3. PANELBOARDS SHALL BE LABELED WITH A UL SHORT-CIRCUIT RATING. WHEN SERIES RATINGS ARE APPLIED WITH INTEGRAL OR REMOTE UPSTREAM DEVICES, A LABEL OR MANUAL SHALL BE PROVIDED. IT SHALL STATE THE CONDITIONS OF THE UL SERIES RATINGS INCLUDING: a. SIZE AND TYPE OF UPSTREAM DEVICE. b. UL RECOGNIZED BRANCH DEVICES THAT CAN BE USED. c. UL SERIES SHORT-CIRCUIT RATING.	4. THE CEILING MOUNTED ANALOG SMOKE SENSORS SHALL BE SILENT KNIGHT MODEL SD505-APS, SENSORS SHALL BE OF THE SOLID STATE PHOTO-ELECTRIC TYPE, AND SHALL OPERATE ON LIGHT SCATTERING, PHOTO-DOSE PRINCIPLE. SENSORS SHALL BE LISTED BY UNDERWRITERS LABORATORIES AND APPROVED BY FACTORY MUTUAL UNDER THE CURRENT STANDARDS FOR PHOTO-ELECTRIC TYPE SMOKE SENSORS. FOR EASE OF MAINTENANCE AND INSTALLATION, SENSORS SHALL BE DESIGNED FOR TWIST LOCK MOUNTING TO A INDIVIDUAL BASE ASSEMBLY HAVING SCREW TERMINALS FOR EXTERNAL WIRING CONNECTIONS.	5. MODEL SD505-6AB ADDRESSABLE BASE ASSEMBLY SHALL BE PROVIDED WITH EACH SMOKE AND HEAT SENSOR UNLESS OTHERWISE NOTED ON THE PLANS. EACH SENSOR BASE ASSEMBLY SHALL BE EQUIPPED WITH AN OPTIONAL LOGGING MECHANISM TO PREVENT UNAUTHORIZED REMOVAL OF THE SENSOR AND SHALL MOUNT ON A STANDARD 3-1/2" (2" ROUND, 4" SQUARE OR OCTAGONAL) OUTLET BOX. BOX DEPTH SHALL BE SELECTED ON THE BASIS OF THE NUMBER OF CONDUCTORS CONNECTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE.	6. HEAT SENSORS, WHEN SHOWN ON THE CONSTRUCTION DOCUMENTS, SHALL BE SILENT KNIGHT MODEL SD505-APS, MOUNT TO SD505-6AB SENSOR BASE.	7. THE DUCT SMOKE SHALL BE SILENT KNIGHT MODEL SD505-ADHR WITH APPROPRIATE SAMPLING TUBES. ALL DUCT SMOKE SENSORS SHALL HAVE A MODEL SD505-DTS REMOTE ALARM INDICATOR, DOORS IN VIEW AND VISUAL INDICATOR. UL TEST STATE SHALL BE SHOWN ON THE PLANS. THE SPECIFIC NAME AND LOCATION OF THE ALARM DEVICE SHALL BE INDICATED.	8. THE CONTRACTOR UNDER THIS DIVISION IS RESPONSIBLE FOR PROVIDING ALL SIGNALS INTERNAL OR EXTERNAL TO ALL LOCATIONS DESIGNATED OR REQUIRED BY LOCAL, STATE OR NATIONAL FIRE CODES GOVERNING BUILDINGS OF THE TYPE AND DESCRIPTION INVOLVED.	9. THE FIRE ALARM SYSTEM SHALL BE AS DESCRIBED HEREIN AND AS SHOWN ON THE CONSTRUCTION DOCUMENTS. ACTUATION OF ANY ALARM INITIATING DEVICE SHALL CAUSE ALL AUDIBLE ALARM DEVICES TO SOUND CONTINUOUSLY. ALARM INITIATING DEVICES SHALL BE GROUPED IN ZONES. ANY ZONE INTO WHICH THE ALARM SHALL BE INDICATED BY A LIGHTED RED LED ON THE ZONE MODULE INVOLVED. THE ACTUATION OF ANY ALARM INITIATING DEVICE SHALL ALSO SHUTDOWN CERTAIN AIR HANDLING UNITS AS MAY BE DESIGNATED, RETURN ELEVATORS TO THE FIRST OR GROUND FLOOR, AND ANNUNCIATE THE ALARM CONDITION ON THE ANNUNCIATOR(S) LOCATED AS SHOWN ON THE CONSTRUCTION DOCUMENTS.	10. THE GENERAL ALARM DEVICES MAY BE SILENCED BY AUTHORIZED PERSONNEL ONLY BY ENTERING A LOCKED AND CONTROLLED REMOTE CONTROL. THE REMOTE CONTROL SHALL SWITCH, BUT ANY SUBSEQUENT ALARMS SHALL SOUND ALL SIGNALS. OPERATION OF THIS SWITCH SHALL BE INDICATED BY A TROUBLE LIGHT AND AUDIBLE SIGNAL. SYSTEM SHALL BE COMPLETELY SUPERVISED, AND ANY OPEN, SHORT, OR GROUNDED CONDITION WILL CAUSE THE TROUBLE LIGHT TO BE FLASHING AND THE TROUBLE LIGHT SIGNAL TO SOUND. THIS SHALL REMAIN UNTIL TROUBLE CONDITION HAS BEEN CORRECTED.	11. THE MAIN FIRE ALARM CONTROL PANELS SHALL BE SILENT KNIGHT FAHREMYT IPF 100 AND/OR TOWER WITH 40 CHARACTER LCD ANNUNCIATOR. INSTALLED AS SHOWN ON THE CONSTRUCTION DOCUMENTS. ALL ZONE LIGHTS, TROUBLE LIGHTS, TROUBLE SIGNALS, SILENCING SWITCHES AND LIGHTS, AND RESET SWITCHES SHALL BE MOUNTED IN SURFACE CABINET AND CONTAIN THE FOLLOWING ITEMS: a. GREEN POWER ON LIGHT b. MANUAL EVACUATION SWITCH c. SYSTEM RESET SWITCH d. TROUBLE LIGHTS e. TROUBLE SILENCING SWITCH f. TONE ALERT TROUBLE SIGNAL g. AUXILIARY RELAYS WITH Bypass SWITCHES h. PROVISION FOR REMOTE RESET i. ZONES SHALL BE AS INDICATED ON CONSTRUCTION DOCUMENTS. A SCHEDULE OF ANNUNCIATION ENGRAVING SHALL BE FURNISHED FOR ARCHITECT'S AND ENGINEER'S APPROVAL. MAIN CONTROL PANEL SHALL HAVE CAPACITY TO INDICATE ZONES IN THIS BUILDING PLUS REMOTE BUILDING BUILDINGS, AND FROM THE GENERATOR, FIRE PUMP AND TRANSFER SWITCHES.	12. CONTROL MODULES SHALL BE PROVIDED FOR THE OPERATING AND INCLUDING FUNCTIONS OF THE FIRE ALARM SYSTEM. THESE FUNCTIONS SHALL INCLUDE SYSTEM RESET, ALARM LOCKOUT-IN, ALARM RESOLUD AND SILENCING OF THE LIFE SAFETY SYSTEM TROUBLE LED, TONE ALERT, AND LED TEST. UPON HAVING DETECTED AN ALARM CONDITION, A ZONE SHALL REPORT ITS STATUS TO THE CONTROL MODULE. THIS ALARM CONDITION SHALL CAUSE THE ALARM TO SOUND AND SILENCING OF THE LIFE SAFETY SYSTEM OPERATION, IT SHALL ALSO CAUSE THE SOUNDING OF ALARM SIGNALS, THE ACTIVATION OF THE GAMEWELL BOX, OR THE OPERATION OF THE FAN CONTROL RELAYS. WHEN THE ACKNOWLEDGE SWITCH IS PRESSED, THE ZONE'S ALARM LED SHALL CEASE TO FLASH AND REMAIN ILLUMINATED. AT THIS TIME, THE SIGNALS SHALL ALSO BE SILENCED. THE ACTIVATION OF ANOTHER ZONE SHALL REPLACE THE ENTIRE ALARM PROCESS, THIS CAUSING THE SIGNALS TO "RESOUND." ALL ALARM AND TROUBLE EVENTS SHALL BE AUTOMATICALLY STORED INTO THE SYSTEM HISTORY LOG AND MAY BE REVIEWED BY OPERATOR WITH PROPER AUTHORIZATION CODE.	13. THE ZONE ALARM INITIATING CIRCUIT MODULES SHALL PROVIDE EIGHT ELECTRICALLY SUPERVISED NORMALLY OPEN CIRCUITS PER MODULE FOR CURRENT LISTED DEVICES MONITORING FOR ALARM TROUBLE (SHORT OR OPEN) AND GROUND FAULT. EACH MODULE SHALL PROVIDE LCD ANNUNCIATION FOR ALARM, OPEN TROUBLE ANNUNCIATOR OUTPUTS, ALARM AND TROUBLE PRINTOUTS, AUXILIARY ALARM CONTACTS (N/O – 2 AMPERE RESISTIVE), AND ALARM AND TROUBLE RESOLUD WITH FLASHER (KNOWLEDGE FROM CONTROL). THE MODULE SHALL BE CAPABLE OF POWERING CURRENT LIMITED TWO-WIRE SMOKE SENSORS. THE MODULE SHALL BE COMPLETELY PLUGGABLE AND INHERENTLY POWER LIMITED (LIMITED ENERGY). PROVIDE THE NUMBER OF ZONES REQUIRED PLUS ONE PERCENT. PROVIDE PRIOR TO THE REMOVAL OF THE MODULE. MODULE SHALL PROVIDE 127 ADDRESSES FOR MONITOR OR CONTROL POINTS PER LOOP.	14. THE NAC SIGNAL CIRCUITS SHALL BE CAPABLE OF SUPPLYING A MINIMUM OF (2.5) AMPERES OF SIGNAL CURRENT TO EACH SIGNAL CIRCUIT. IT SHALL SUPPLY POWER VIA A TWO-WIRE SUPERVISED CIRCUIT AND INDICATE OPEN OR SHORTED FAULTS ON THE LCD ANNUNCIATOR. THE MODULE SHALL BE PROTECTED BY A FUSE.	15. THE POWER SUPPLY MODULE SHALL PROVIDE 6 AMPERES OF CONTINUOUS FLUSHED POWER OF THE PROPER VOLTAGE. THE POWER SUPPLY SHALL BE CAPABLE OF FURNISHING THE SYSTEM POWER AND POWER FOR DEVICES SUCH AS SMOKE SENSORS, AUXILIARY RELAYS, DOOR HOLDERS, ETC. IT SHALL PROVIDE A 12VDC BATTERY TROUBLE AND TROUBLE AND RADIO SUPPLY TROUBLE ANNUNCIATION ON THE LCD ANNUNCIATOR ALL VIEWABLE ON FRONT OF ENCLOSURE. A 250 VA TRANSFORMER SHALL BE PROVIDED IN THE CONTROL PANEL.	16. N AUTOMATIC DUAL-RATE BATTERY CHARGER MODULE SHALL BE INSTALLED IN THE CONTROL PANEL WHICH SHALL BE CAPABLE OF CHARGING EITHER A GEL OR WET CELL BATTERY. A CONSTANT TRICKLE CHARGE SHALL CONTINUOUSLY BE APPLIED TO THE BATTERY IN ORDER TO MAINTAIN IT AT FULL CHARGE. CHARGE RATE ADJUSTING THE TRICKLE CHARGE RATE SHALL ALSO BE PROVIDED IN ORDER TO SUPPLY THE SELECTED BATTERY WITH THE EXACT CHARGE RATE IT REQUIRES. IN THE EVENT OF A FAILURE OF THE CHARGER, THE CHARGER FAILURE SHALL BE INDICATED ON THE BATTERY CAPACITY DROP BELOW SPECIFIED LIMITS. THE CHARGER SHALL AUTOMATICALLY CHANGE TO HIGH RATE CHARGE, AND AN LED SHALL ILLUMINATE. MAINTENANCE FREE BATTERIES SHALL BE PROVIDED TO DELIVER 24 HOURS OF STANDBY POWER.	17. A BATTERY MONITOR MODULE SHALL BE PROVIDED TO MONITOR THE CHARGER AND THE BATTERY MOUNTED WITHIN THE CONTROL PANEL. SHOULD THE BATTERY VOLTAGE BECOME EXCESSIVELY LOW, EXCESSIVELY HIGH OR NOT BE CONNECTED AT ALL, THE BATTERY MONITOR MODULE SHALL BE ACTIVATED AND THE BATTERY TROUBLE LED SHALL ILLUMINATE.	18. THE AUXILIARY FLEXPLUX SHALL HAVE THE ABILITY TO BE CONFIGURED FOR NAC, INITIATING ZONE, OR RELAY OUTPUT. AT 3 AMPERES, THESE SIGNALS SHALL BE USED FOR OPERATING EXTERNAL CIRCUITS INDEPENDENT OF THE FIRE ALARM SYSTEM (I.E., FAN CONTROLS, DOOR RELEASE, ETC.).	19. THE CONTROL CABINET SHALL BE SURFACE MOUNTED AND ACCOMMODATE ALL THE MODULES, RELAYS, TERMINAL CONNECTIONS, AND BATTERIES. PROVIDE FOR THE PROPER OPERATION OF THE SYSTEM. THE ENCLOSURE SHALL BE EQUIPPED WITH AN EXTERIOR DOOR AND FRAME ASSEMBLY WHICH SHALL BE FITTED WITH A LOCK AND A TRANSPARENT DOOR PANEL, TO PERMIT FULL VIEWING OF THE VARIOUS MODULE LIGHTS AND SWITCHES.	20. REMOTE ANNUNCIATOR – THE SERIAL ANNUNCIATOR SHALL PROVIDE AN ALPHANUMERIC, 80 CHARACTER LIQUID CRYSTAL DISPLAY (LCD) THAT PROVIDES CLEAR LANGUAGE INFORMATION AS TO THE FIRST PANEL STATUS (ALARM, TROUBLE, ETC.), TYPE OF ALARM (SMOKE SENSOR, PULL STATION, ETC.), NUMBER OF ALARMS IN THE SYSTEM, AND A CUSTOM LOCATION LABEL. THE ANNUNCIATOR(S) SHALL HAVE A GREY OR RED FINISH AS DIRECTED BY THE ARCHITECT. THE ANNUNCIATOR SHALL COMMUNICATE TO THE CONTROL PANEL OVER 4 CONDUCTOR #16AWG WIRE AND A POWER WIRE. SHALL BE 24 VDC AND BE FUSED AT THE CONTROL PANEL. THE WIRED ANNUNCIATOR SHALL NOT BE CONSIDERED AS EQUAL. STATUS INFORMATION OF EACH DEVICE MAY BE INDIVIDUALLY DISPLAYED TO INVESTIGATE SPECIFIC POINT DETAIL. REMOTE ANNUNCIATOR MAY NOT BE REQUIRED ON ALL PROJECTS; REFER TO THE PROJECT'S SPECIFICATIONS. IF WIRING, PROGRAMMABLE CONTROL SHALL BE PROVIDED FOR THE FOLLOWING FUNCTIONS: a. SYSTEM RESET b. ALARM SILENCE c. TROUBLE SILENCE d. MANUAL EVACUATION e. CITY DISCONNECT	21. EXAMINE AREA TO RECEIVE MAIN CONTROL PANEL, TO ASSURE ADEQUATE SPACE AND CLEARANCES.	22. THE CONTRACTOR SHALL FURNISH AND INSTALL IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS ALL WIRING, CONDUIT, AND OUTLET BOXES FOR THE ERECTION OF A COMPLETE SYSTEM AS DESCRIBED HEREIN AND AS SHOWN ON THE CONSTRUCTION DOCUMENTS. ALL WIRING SHALL BE IN CONDUIT OF THE SAME APPROVED TYPE AS USED FOR ELECTRICAL LIGHTING AND POWER WIRING. ALL WIRING SHALL BE SPECIFIED BY THE MANUFACTURER. BEFORE INSTALLATION, A COLOR CODING SYSTEM SHALL BE COORDINATED WITH THE MANUFACTURER AND ADHERED TO. ESTABLISH STANDARDS OF QUALITY FOR MATERIALS AND PERFORMANCE. THE MANUFACTURER SHALL BE IDENTIFIED BY THE MANUFACTURER'S NAME, ADDRESS, AND PHONE NUMBER. A SPECIFIC MANUFACTURER OR A CATALOG NUMBER DOES NOT WAIVER ANY REQUIREMENT OR PERFORMANCE OF INDIVIDUAL COMPONENTS DESCRIBED IN THE SPECIFICATIONS.	23. DESIGN SHALL INCLUDE REPERF-SIMULATED RADIO PROPAGATION MODELING WITH HEAT MAPS SHOWING DETECTED SIGNAL COVERAGE LEVELS WITHIN THE BUILDING. THE EMMAP DESIGN SHALL BE DONE BY IMAVE CERTIFIED PERSONNEL.	24. ASSEMBLY AND INSTALLATION OF ALL COMPONENTS OF THE EMERGENCY RESPONDER RADIO COMMUNICATION ENHANCEMENT SYSTEM SHALL COMPLY WITH ALL APPLICABLE SECTIONS OF THE NATIONAL ELECTRICAL CODE.	25. SURVIVABILITY FROM ATTACK BY FIRE SHALL MEET REQUIREMENTS OF NFPA 1221 2019 EDITION AS REQUIRED BY THE LOCAL JURISDICTION.	26. NFPA 1221, 2019 EDITION 3.3.10: BACKDRIVE: A COMMUNICATIONS CABLE IN AN IN-BUILDING RADIO ENHANCEMENT SYSTEM THAT CARRIES WIDEBAND SIGNALS IS IMPORTANT TO THE ENTIRE BUILDING, FROM THE DONOR ANTENNA, THROUGH THE AMPLIFIERS, AND TO DISTRIBUTION ANTENNA LINES.	27. NFPA 1221, 2019 EDITION 9.6.2.3: BACKDRIVE CABLES SHALL BE ROUTED THROUGHOUT THE BUILDING ENCLOSURE TO THE BUILDING'S FIRE RATING.	28. THE SYSTEM MUST COMPLY WITH ALL APPLICABLE SECTIONS OF THE FCC RULES. SIGNAL BOOSTER / FIBER DAS MASTER/REMOTE SHALL HAVE FCC CERTIFICATION PRIOR TO INSTALLATION.	29. ANTENNA INSTALLATION SHALL BE MAINTAINED BETWEEN THE DONOR ANTENNA AND ALL INSIDE ANTENNAS (O.D.S.) TO A MINIMUM OF 20dB UNDER ALL OPERATING CONDITIONS.	30. TECHNICAL SPECIFICATIONS AND PERFORMANCE REQUIREMENTS 1. THE SYSTEM SPECIFIED SHALL BE BASED UPON THE WESTELL, FLEXBY BY HONEYWELL, OR TOWERJONES LINE OF PUBLIC SAFETY SIGNAL BOOSTERS / FIBER DAS OR AN EQUIVALENT UL2524 2ND EDITION LISTED, FCC CERTIFIED, AND IFCC, NFPA 1221, AND NFPA 72 COMPLIANT LINE.	31. THE SYSTEM SHALL BE PUBLIC SAFETY TYPE SIGNAL BOOSTER OR FIBER DAS MASTER/REMOTE.	32. SIGNAL BOOSTER OR FIBER DAS MASTER/REMOTE SHALL SUPPORT BOTH CLASS A AND CLASS B OPERATION.	33. SIGNAL BOOSTER OR FIBER DAS MASTER/REMOTE SHALL FUNCTION IN THE CLASS OF OPERATION (A OR B) AS DIRECTED BY THE AHA'S EMERGENCY RESPONDER RADIO SYSTEM WHICH THE BOOSTER IS INTENDED TO AMPLIFY, THE AHA, OR THE FCC.	34. ALL SIGNAL BOOSTER COMPONENTS SHALL BE CONTAINED IN A NEMA 4-TYPE WATERPROOF CABINET.	35. BATTERY SYSTEMS SHALL BE CONTAINED IN A NEMA 3R OR HIGHER-RATED CABINET.	36. THE SECONDARY POWER SUPPLIES, BATTERY CHARGERS AND SYSTEM MONITORING SHALL BE FULLY COMPLIANT WITH UL2524 2ND EDITION, IFCC, NFPA 1221, AND NFPA 72.	37. ALL SIGNAL BOOSTER COMPONENTS SHALL BE FULLY COMPLIANT WITH FCC CERTIFICATION PRIOR TO INSTALLATION. THE EQUIPMENT FCC ID MUST BE DISPLAYED ON THE PRODUCT AS REQUIRED BY THE FCC.	38. THE DIGITAL SIGNAL BOOSTER SHALL BE CAPABLE OF FIELD CONFIGURATION VIA PROGRAMMABLE SOFTWARE OR A LOCAL WIRELESS, WEB-BASED INTERFACE FOR THE FREQUENCY CHANNELS WITH ADJUSTABLE BANDWIDTHS AS SPECIFIED BY THE AHA.	39. SIGNAL BOOSTERS SHALL HAVE ISOLATION SUPPRESSION CIRCUITRY TO PROTECT THE PUBLIC SAFETY RADIO SYSTEM FROM INTERFERENCE OR OTHER CAUSES. THIS SIGNAL BOOSTER CIRCUITRY SHALL ALLOW REAL TIME AUTOMATED OSCILLATION CORRECTION AND TOLERANCE. DETECTION CIRCUITS SHALL BE ADJUSTED OR REPROGRAMMED TO CORRECT FOR TOLERANCE. DETECTION CHANGES AND CLOSURES, IN EXPOSED LOCATIONS AS LONG CEILING, OR ABOVE NORMAL TRAFFIC LEVEL AND WHERE NOT SUBJECT TO ACCIDENTAL DAMAGE OR ABUSE.	40. SIGNAL BOOSTERS MUST HAVE UPLINK AND DOWNLINK SQUELCH PER CHANNEL PER TIMESLOT.	41. SIGNAL BOOSTERS SHALL BE ADJUSTED TO A MINIMUM OF 850B +/- 2.00B AND THE GAIN SHALL BE ADJUSTED TO A MINIMUM OF 20DB. THE SIGNAL BOOSTER SYSTEM GAIN SHALL BE SET AND DOCUMENTED AT THE TIME OF THE FINAL SYSTEM TEST.	42. MAXIMUM PROPAGATION DELAY OF THE SIGNAL BOOSTER SYSTEM SHALL BE ADJUSTABLE IN THE SIGNAL BOOSTER TO COMPLY WITH THE REQUIREMENTS OF THE FCC. THE SIGNAL BOOSTER SHALL OFFER FILTER DELAY OPTIONS. MAXIMUM PROPAGATION DELAY SHALL BE WITHIN THE MINIMUM RANGE OF 3.5μS (MICROSECONDS) TO A MAXIMUM OF 61.5μS (MICROSECONDS).	43. SIGNAL BOOSTER SHALL PRODUCE NO MORE THAN A MAXIMUM OF 90DB THROUGHOUT ITS PUBLISHED OPERATING UPLINK GAIN RANGE.	44. A DEDICATED SUPERVISORY CONTROL PANEL SHALL BE PROVIDED WITHIN THE EMERGENCY COMMUNICATION CENTER NEXT TO THE FIRE ALARM PANEL / ANNUNCIATOR OR OTHER LOCATION AS DESIGNATED BY AHA TO ANNUNCIATE THE STATUS OF ALL SIGNAL BOOSTER LOCATIONS. THE MONITORING PANEL SHALL PROVIDE VISUAL AND LABELED INDICATION OF THE FOLLOWING FOR EACH SIGNAL BOOSTER: a. NORMAL AC POWER b. ACTIVE RF-EMITTING DEVICE MALFUNCTION c. DONOR ANTENNA MALFUNCTION d. LOSS OF NORMAL AC POWER e. FAILURE OF BATTERY CHARGER f. LOW BATTERY CAPACITY g. ACTIVE SYSTEM COMPONENT MALFUNCTION.	45. THE SIGNAL BOOSTER SYSTEM SHALL INCLUDE BUILT-IN AUTOMATIC SUPPRESSION OF MALFUNCTIONS OF THE SIGNAL BOOSTER AND BATTERY SYSTEMS AS PER FCC, NFPA 1221, AND NFPA 72. NON-DEM OPERATING MODES AND MODIFICATIONS TO COMPLY WITH THIS SPECIFICATION SHALL NOT BE ACCEPTABLE.	46. SIGNAL BOOSTERS SHALL BE MONITORED BY A LISTED FIRE ALARM CONTROL UNIT, OR BY A DEDICATED SUPERVISORY CONTROL PANEL. THE MONITORING PANEL SHALL BE SET AND ATTENDED ON SITE LOCATION.	47. SIGNAL BOOSTERS SHALL BE EQUIPPED WITH UNIVERSAL NORMALLY OPEN RELAYS FOR CONNECTION TO EXTERNAL MONITORING MODULES. THE MONITORING MODULE SHALL BE CAPABLE OF AUTOMATIC SUPERVISORY SIGNALS ON THE FIRE ALARM CONTROL UNIT SHALL BE ACTIVATED BY THE FOLLOWING CONDITIONS: i. LOSS OF NORMAL AC POWER ii. BATTERY CHARGER FAILURE iii. LOW BATTERY CAPACITY iv. DONOR ANTENNA MALFUNCTION v. ACTIVE RF-EMITTING DEVICE MALFUNCTION vi. ACTIVE SYSTEM COMPONENT MALFUNCTION	48. THE COMMUNICATION LINK BETWEEN THE FIRE ALARM SYSTEM AND THE SIGNAL BOOSTERS SHALL BE MONITORED FOR INTERFERENCE.	49. EXTERNAL FILTERS, DUPLEXERS, POWER SUPPLIES OR OTHER NON-DEM ADDITIONS OR MODIFICATIONS OF THE ORIGINAL EQUIPMENT SHALL NOT BE ACCEPTABLE WITH THE EXCEPTION WHERE TECHNICALLY REQUIRED SO LONG AS IT DOES NOT VIOLATE THE UL2524 2ND EDITION REQUIREMENTS OF THE EQUIPMENT. THE EQUIPMENT SHALL BE MANUFACTURED OR CERTIFIED BY THE MANUFACTURER.	50. EARLY COMPLETION OF THE IN-BUILDING EMERGENCY RESPONDER RADIO COMMUNICATION ENHANCEMENT SYSTEM WILL BE REQUIRED AS TO PERMIT A CERTIFICATE OF OCCUPANCY TO BE OBTAINED IN A TIMELY MANNER.	51. ANY REMOTE NECESSARY POWER SOURCE SHALL BE SUPPLIED FROM A DEDICATED TWENTY (20) AMPERE BRANCH CIRCUIT AND COMPLY WITH NFPA-70 NATIONAL ELECTRICAL CODE, NFPA 72 AND NFPA 1221.	52. A DEDICATED TWENTY-TWO (22) AMPERE BRANCH CIRCUIT WITH A DEDICATED BATTERY CHARGER POWERED BY A DEDICATED TWENTY (20) AMPERE BRANCH CIRCUIT. THE SECONDARY POWER SUPPLY SHALL POWER ON AUTOMATICALLY WHEN THE PRIMARY POWER SUPPLY IS LOST. THE SECONDARY POWER SUPPLY SHALL BE CAPABLE OF OPERATING THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM FOR A PERIOD OF AT LEAST 12 HOURS. THE BATTERY SYSTEM SHALL AUTOMATICALLY CHARGE IN THE PRESENCE OF EXTERNAL POWER INPUT. BATTERY CHARGER AND ALL OTHER ELECTRICAL COMPONENTS SHALL BE FULLY ENCLOSED IN A WATERPROOF NEMA 3R OR HIGHER-RATED ENCLOSURE. BATTERIES SHALL BE ENCLOSED IN A NEMA 3R OR HIGHER-RATED ENCLOSURE. EXTERNAL UPS (UNINTERRUPTIBLE POWER SUPPLIES) ARE NOT ACCEPTABLE.	53. RF COAXIAL CABLE SHALL BE A LISTED, CUP PLENUM, ARMORED PLENUM, OR 2-HOUR FIRE RATED PLENUM CABLE. THE CABLE SHALL BE USED FOR THE ENTIRE LENGTH OF THE CABLE. METALLIC RACEWAY: THE CABLE CLASSIFICATION SHALL BE CLEARLY MARKED ON THE OUTER SURFACE OF THE CABLE REGULAR INTERVALS.	54. THE CABLE SHALL BE PROTECTED BY AN ENCLOSURE THAT MATCHES THE BUILDING'S FIRE RATING.	55. ALL INSTALLED SYSTEMS WILL NEED PRIOR WRITTEN APPROVAL FROM THE FCC LICENSE HOLDER OF THE SYSTEMS BEING RE-AMPLIFIED AND MUST MEET THEIR ESTABLISHED CRITERIA FOR INSTALLATION PRIOR TO THE SYSTEM INSTALLATION.	56. INSTALLED SYSTEMS SHALL BE REGISTERED WITH THE FCC SIGNAL BOOSTER REGISTRY.	57. ACCEPTANCE AND TEST PROCEDURES 1. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	58. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	59. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	60. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	61. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	62. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	63. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	64. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	65. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	66. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	67. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	68. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	69. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	70. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	71. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS OF GAIN FROM WHEN THE SYSTEM WAS ORIGINALLY COMMISSIONED. 4. ALL POWER SUPPLIES AND BATTERIES SHALL BE TESTED FOR LOSS OF POWER AND COMMUNICATION FAILURE. 5. UPON COMPLETION OF ANNUAL TESTING A REPORT SHALL BE PROVIDED TO THE OWNER AND LOCAL AHA.	72. ACCEPTANCE TESTING FOR AN IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE AN INTEGRAL COMPONENT OF THE SYSTEM INSTALLATION. 2. THE COVERAGE TESTING SHALL BE DONE IN ACCORDANCE WITH FCC 2021 EDITION, NFPA 1221 2019 EDITION, AND AS REQUIRED BY THE LOCAL AHA. 3. ALL TESTS SHALL BE CONDUCTED, DOCUMENTED, AND SIGNED BY A PERSON IN POSSESSION OF A CURRENTLY VALID FCC LICENSE. 4. ALL TEST RECORDS ALONG WITH SYSTEM DIAGRAMS, EMMAP DESIGN, EQUIPMENT SPECIFICATIONS, USER MANUALS, RF LINK BUDGET CALCULATIONS, BATTERY BACKUP, AND OTHER SUPPORTING DOCUMENTS SHALL BE SUBMITTED UPON COMPLETION OF THE PROJECT, AND AS REQUIRED BY THE AHA. 5. ANNUAL MAINTENANCE AND PROOF OF COMPLIANCE 1. THE IN-BUILDING TWO-WAY EMERGENCY RESPONDER COMMUNICATION ENHANCEMENT SYSTEM SHALL BE MAINTAINED IN ACCORDANCE WITH FCC. 2. THE SYSTEM SHALL BE TESTED ANNUALLY AS PART OF ROUTINE MAINTENANCE OR WHEN STRUCTURAL CHANGES, ADDITIONS OR SPACE LAYOUT CONFIGURATIONS CAN AFFECT THE INITIAL VOLTAGE AND POWER LEVELS. 3. AS PART OF ANNUAL TESTING THE SIGNAL BOOSTER SHALL BE VERIFIED FOR LOSS
--	--	---	--	--	--	--	--	--	--	---	--	--	---	--	---	---	--	---	--	--	--	---	--	--	--	--	--	--	--	---	---	--	---	--	--	--	--	---	---	--	--	---	---	---	---	---	---	--	--	---	--	--	---	--	---	---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	---

LUMINAIRE SCHEDULE						
TYPE	LAMP	WATTAGE	VOLTAGE	DIMMING TYPE	DESCRIPTION	EQUIVALENT MANUFACTURER/REMARKS
D-1			120		LED DOWNLIGHT USED IN CLUBROOM.	
D-1A			120		LED DOWNLIGHT USED IN FIRST FLOOR CORRIDOR.	
D-2			120		LED DOWNLIGHT USED THROUGHOUT THE BUILDINGS.	
D-4			120		LED DOWNLIGHT USED IN CLUBROOM.	
D-5			120		LED DOWNLIGHT USED IN OUTDOOR CORRIDOR.	
D-6			120		LED DOWNLIGHT USED IN CORRIDORS.	
ESC-2			120		LED EXTERIOR LIGHT.	
S-2			120		LED STRING LIGHT USED IN CLUBROOM.	
S-3			120		LED SQUARE LIGHT USED IN CORRIDOR.	
S-4			120		LED LIGHT USED IN PUBLIC BATHROOMS.	
P-1			120		LED SPHERE LIGHT USED IN CLUBROOM AND LOBBY AREA.	
P-6			120		LED STRIP LIGHT USED IN FITNESS AREA.	
P-7			120		LED STRIP LIGHT USED IN FITNESS AREA.	
P-8			120		LED STRING LIGHT USED ABOVE FITNESS AREA.	
SM-2			120		LED FIXTURE USED IN OFFICES.	
SM-3			120		LED FIXTURE USED IN PUBLIC BATHROOMS.	
U-1			120		LED STRIP LIGHT USED IN HOUSE AREAS.	
U-2			120		LED STRIP LIGHT USED IN STAIRWAYS, WITH ON-FIXTURE MOTION SENSOR.	
WS-1			120		LED SQUARE LIGHT USED IN CORRIDORS.	
X1						
X2						
X3						
LUMINAIRE SCHEDULE GENERAL NOTES:						
1. VERIFY ALL LUMINAIRE COLORS, TRIMS, LENGTHS, ETC. WITH THE ARCHITECT/OWNER/DEVELOPER/DESIGNER PRIOR TO PLACING FINAL PURCHASE ORDERS. SUBMISSION OF SHOP DRAWINGS WILL BE INTERPRETED AS HAVING BEEN COORDINATED WITH THE AFOREMENTIONED PARTIES.						
2. PROVIDE ALL LENGTHS, FEEDS, ACCESSORIES, CONNECTORS, WIRING, POWER SUPPLIES, DRIVERS, ETC. FOR A COMPLETE INSTALLATION. VERIFY THE COMPLETE BILL OF MATERIAL WITH MANUFACTURER'S REPRESENTATIVE AND ENSURE ALL EQUIPMENT IS INCLUDED IN BID PRICE. COORDINATE INSTALLATION WITH ARCHITECTURAL DETAILS.						
3. VERIFY FINAL LUMINAIRE LOCATIONS WITH OTHER CEILING MOUNTED EQUIPMENT SUCH AS DIFFUSERS, FIRE ALARM DEVICES, SPEAKERS, ETC., WITH ARCHITECTURAL REFLECTED CEILING PLANS.						
4. VERIFY EXACT MOUNTING HEIGHT AND LOCATIONS OF ALL WALL MOUNTED AND PENDANT MOUNTED LUMINAIRES WITH ARCHITECTURAL PLANS AND ELEVATIONS PRIOR TO ROUGH-IN.						
5. ANY PROPOSED ALTERNATE LUMINAIRES SHALL BE APPROVED BY THE ARCHITECT/OWNER/DEVELOPER/DESIGNER PRIOR TO FINAL BID PRICING.						
6. SHOULD THE CONTRACTOR PROPOSE TO FURNISH MATERIALS, EQUIPMENT, AND DEVICES, OTHER THAN THOSE SPECIFIED AND LISTED, THE CONTRACTOR SHALL SUBMIT A WRITTEN REQUEST FOR SUBSTITUTIONS, TO THE ENGINEER AT LEAST TEN (10) BUSINESS DAYS PRIOR TO BID OPENING. THE REQUEST SHALL BE AN ALTERNATE TO THE ORIGINAL BID AND SHALL INCLUDE A COMPLETE SPECIFICATIONS CUT SHEET SUBMITTAL AS OUTLINED IN THE SPECIFICATIONS, COMPLETE WITH DESCRIPTIVE (MANUFACTURER, BRAND NAME, CATALOG NUMBER, ETC.) AND TECHNICAL DATA FOR ALL ITEMS. INDICATE ANY ADDITIONS OR DEDUCTIONS TO THE CONTRACT PRICE WITH THE SUBSTITUTION SUBMITTAL AND ON THE BID FORM.						
7. ANY FINAL SELECTED/INSTALLED LIGHT FIXTURES WITHOUT A SPECIFICATION (OR TO BE SPECIFIED LATER BY ARCHITECT/OWNER/DEVELOPER/DESIGNER) LISTED IN THIS SCHEDULE SHALL NOT EXCEED THE WATTAGE LISTED, SHALL NOT HAVE A LOWERED DELIVERED LUMENS (IF LISTED), AND SHALL MATCH THE COLOR TEMPERATURE (IF LISTED).						



TYPICAL DEVICE MOUNTING DETAIL
NO SCALE

TYPICAL DEVICE MOUNTING DETAIL GENERAL NOTES:

- A. ALL MOUNTING HEIGHTS SHALL BE MEASURED FROM FINISHED FLOOR TO THE CENTERLINE OF DEVICE EXCEPT FIRE ALARM A/V DEVICES.
- B. NO WIRING DEVICES OR OUTLET BOXES SHALL BE MOUNTED BACK TO BACK.
- C. ALL MOUNTING DEVICES SHALL BE INSTALLED AT MOUNTING HEIGHTS AS INDICATED ON THIS DETAIL UNLESS OTHERWISE NOTED.
- D. FOR ALL ELEVATIONS (WHERE APPLICABLE), CASEWORK DETAILS, FIRE WALLS, SMOKE WALLS, LOCATION OF COUNTERTOP RECEPTACLES, LIGHTING FIXTURE SWITCHES, TELEPHONE ROUGH-INS, HEADWALLS, ETC., SEE ARCH DRAWINGS. WHERE NO ARCHITECTURAL ELEVATIONS OR DETAILS OCCUR, THE ELECTRICAL CONTRACTOR SHALL USE MEANS AND METHODS AS WELL AS THEIR FIELD KNOWLEDGE TO SPOT DEVICES IN THE BEST LOCATIONS FOR THE PROJECT.

ELEVATOR INSTALLATION GENERAL CONSTRUCTION NOTES

1. INCLUDE EXTERNALLY OPERABLE SHUNT TRIP CIRCUIT BREAKERS CAPABLE OF BEING LOCKED IN THE "OFF" POSITION FOR ELEVATOR 3-PHASE POWER FEED (NEC 620.51). PROVIDE WIRING FROM THE FIRE ALARM SYSTEM TO THE CIRCUIT BREAKER FOR SHUNT TRIP ACTIVATION UPON OPERATION OF THE ELEVATOR CONTROL HEAT DETECTORS, UNLESS OTHERWISE DIRECTED BY LOCAL ELEVATOR INSPECTOR (ASME A17.1-102 AND NEC 620.51(B)). ROUTE 120V WIRING THROUGH FIRE ALARM CONTROL PANEL TO MONITOR LOSS OF SHUNT TRIP POWER (TROUBLE ONLY INDICATION). IF BATTERY POWERED LOWERING IS SPECIFIED BY THE ARCHITECT, PROVIDE A NORMALLY CLOSED CONTACT AND WIRING TO ELEVATOR CONTROLLER TO DISCONNECT ADDITIONAL POWER SOURCE (NEC 620.91(C)).
2. INCLUDE 4-PAIR UNSHIELDED TWISTED PAIR CABLE, MINIMUM-CATEGORY 3 FROM CONTROLLER TO NEAREST AVAILABLE TELEPHONE SERVICES FOR CAR EMERGENCY PHONE/INTERCOM (ANSI A-17.1 - 211). COORDINATE EXACT LOCATION OF TELEPHONE SERVICES. **TYPICAL OF EACH ELEVATOR.**
3. INCLUDE FUSIBLE DISCONNECT OR EXTERNALLY OPERABLE CIRCUIT BREAKER CAPABLE OF BEING LOCKED IN THE "OFF" POSITION FOR 120 VOLT SINGLE PHASE FEED (NEC 620.53). PROVIDE A SECOND SWITCH IF A BRANCH CIRCUIT FOR A HEATING OR AIR CONDITIONING POWER SUPPLY IS PROVIDED (NEC 620.54). **TYPICAL OF EACH ELEVATOR.**
4. INCLUDE DEDICATED 20 AMP, 120 VOLT BRANCH CIRCUIT ON FOR CAR LIGHTS, RECEPTACLES, AUXILIARY LIGHTING SOURCE AND VENTILATOR (NEC 620.22). PROVIDE A SECOND SWITCH IF A BRANCH CIRCUIT FOR A HEATING OR AIR CONDITIONING POWER SUPPLY IS PROVIDED (NEC 620.22). **TYPICAL OF EACH ELEVATOR.**
5. INCLUDE WEATHERPROOF DUPLEX RECEPTACLE - (FOR ELEVATOR SERVICING) AND SWITCH FOR LIGHTS. COORDINATE LOCATION IN FIELD WITH ELEVATOR INSTALLER.
6. INCLUDE SMOKE DETECTOR WITH AUXILIARY CONTACTS FOR ELEVATOR RECALL - LOCATE OUTSIDE EACH ELEVATOR LANDING, AT TOP AND BOTTOM OF THE HOISTWAY (2 FEET ABOVE FLOOR) AND IN THE MACHINE ROOM (ANSI A-17.1 - 211.3b).
7. INCLUDE FIXED TEMPERATURE HEAT DETECTOR AT SETTING LESS THAN SPRINKLER HEAD TO BE MOUNTED ADJACENT TO HEAD. HEAT DETECTORS SHALL INITIATE AN AUTOMATIC POWER SHUTDOWN FOR 3-PHASE POWER TO THE ELEVATOR CONTROLLER, UNLESS OTHERWISE DIRECTED BY THE LOCAL ELEVATOR INSPECTOR. LOCATE HEAT DETECTORS IN THE MACHINE ROOM, AT THE TOP OF THE SHAFT AND AT THE BOTTOM OF THE SHAFT (2 FEET ABOVE THE FLOOR).

GENERAL ELECTRICAL NOTES

1. ANY AND ALL "BUILDING STANDARDS" AND/OR "BUILDING SPECIFICATIONS" SHALL BE CONSIDERED AN INTEGRAL PART OF THESE DOCUMENTS AND THE CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN A COPY OF THESE REQUIREMENTS/THIS DOCUMENT AND COMPLY WITH ALL REQUIREMENTS AND STANDARDS CONTAINED WITHIN.
2. THESE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND ARE INTENDED TO CONVEY THE SCOPE OF WORK AND INDICATE GENERAL ARRANGEMENT OF LIGHTING FIXTURES, DEVICES, CONTROLS, ELECTRICAL FIXTURES, MOTORS, PANELBOARDS, EQUIPMENT, ETC. THE LOCATIONS OF ALL ITEMS SHOWN ON THESE DRAWINGS OR CALLED FOR IN THE SPECIFICATIONS THAT ARE NOT DEFINITELY FIXED BY DIMENSIONS ARE APPROXIMATE. THE EXACT LOCATIONS NECESSARY TO SECURE THE BEST CONDITIONS AND RESULTS MUST BE DETERMINED AT THE PROJECT. ALL LOCATIONS OF WORK EXPOSED TO VIEW ARE SUBJECT TO APPROVAL OF THE ARCHITECT PRIOR TO INSTALLATION.
3. THE ELECTRICAL CONTRACTOR SHALL VERIFY EXISTING CONDITIONS TO ENSURE THAT ALL NEW WORK WILL FIT INTO THE EXISTING STRUCTURE IN THE MANNER INTENDED AND AS SHOWN ON THE DRAWINGS. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT/OWNERS REPRESENTATIVE PRIOR TO ANY ROUGH-INS, FABRICATIONS, OR PERFORMING ANY WORK IN THE AREA INVOLVING DIFFERENCES. NOTIFICATION SHALL BE IN THE FORM OF A DRAWING OR SKETCH INDICATING FIELD MEASUREMENTS AND NOTES RELATED TO THE AREA.
4. ANY DISCREPANCIES BETWEEN DRAWINGS AND SPECIFICATIONS SHALL BE PROMPTLY BROUGHT TO THE ATTENTION OF THE ENGINEER FOR CLARIFICATION DURING THE BIDDING PERIOD. NO ALLOWANCE SHALL SUBSEQUENTLY BE MADE TO THE CONTRACTOR BY REASON OF THEIR FAILURE TO HAVE BROUGHT SAID DISCREPANCIES TO THE ATTENTION OF THE ENGINEER DURING THE BIDDING PERIOD OR OF ANY ERROR ON THE CONTRACTOR'S PART.
5. ALL EQUIPMENT SHALL BE INSTALLED IN A NEAT, PROFESSIONAL AND WORKMANLIKE MANNER, RECTILINEAR TO BUILDING STRUCTURE.
6. ALL COMPONENTS SHOWN ON THE RISER/ONE-LINE DIAGRAMS, BUT NOT ON THE PLAN OR VICE VERSA, SHALL BE INCLUDED AS IF SHOWN ON BOTH.
7. REVIEW ALL TRADES' CONTRACT DOCUMENTS TO DETERMINE SPECIFIC MOUNTING LOCATIONS FOR ELECTRICAL EQUIPMENT. COORDINATE EXACT MOUNTING LOCATIONS WITH THE ARCHITECT.
8. REFER TO ARCHITECTURAL ELEVATIONS TO DETERMINE EXACT LOCATIONS OF ALL RECEPTACLES, OUTLETS/JACKS, SWITCHES, ETC. LUMINAIRES AND CEILING MOUNTED EQUIPMENT SHALL BE COORDINATED WITH THE ARCHITECTURAL REFLECTED CEILING PLANS.
9. EXACT LOCATION OF MECHANICAL EQUIPMENT THAT REQUIRE ELECTRICAL CONNECTION ARE SHOWN ON THE MECHANICAL DRAWINGS. FIELD VERIFY EXACT LOCATIONS WITH MECHANICAL CONTRACTOR PRIOR TO ANY ROUGH-INS.
10. ALL RACEWAY/CIRCUITING SHALL BE RUN CONCEALED UNLESS SPECIFIED OTHERWISE. CUT/FISH/PATCH WALLS AS REQUIRED. USE OF SURFACE RACEWAY MUST BE APPROVED BY ARCHITECT ALONG WITH PROPOSED ROUTING AND SURFACE RACEWAY TYPE.
11. ALL RACEWAYS RUNNING THROUGH BUILDING EXPANSION JOINTS SHALL BE EQUIPPED WITH EXPANSION FITTINGS.
12. CONDUIT HOME RUNS SHOWN ON THE DRAWING WITH MORE THAN (3) CURRENT CARRYING CONDUCTORS ARE SHOWN DIAGRAMMATICALLY. THIS CONTRACTOR SHALL NOT INSTALL MORE THAN (3) CURRENT CARRYING CONDUCTORS IN A RACEWAY UNLESS NATIONAL ELECTRICAL CODE (N.E.C.), ARTICLE 310.15 DERATING FACTORS ARE APPLIED.
13. ALL LIGHTING AND GENERAL POWER BRANCH CIRCUITS SHALL INCLUDE A SEPARATE NEUTRAL CONDUCTOR, UNLESS SPECIFICALLY NOTED OTHERWISE.
14. THE ELECTRICAL CONTRACTOR SHALL REFER TO THE ELECTRICAL SPECIFICATIONS FOR ACCEPTABLE CONDUIT TYPES/LOCATIONS. ALL CONDUIT SIZES ON THE DRAWINGS ARE BASED ON THE LATEST EDITION OF THE N.E.C. CONDUIT FILL TABLES FOR ELECTRICAL METALLIC TUBING (E.M.T.). CONDUIT SIZES SHALL BE REVISED TO THE SIZE REQUIRED, RELATIVE TO THE ACTUAL CONDUIT TYPE TO BE INSTALLED.
15. IT IS NOT INTENDED THAT THE PLANS INDICATE ALL THE NECESSARY BENDS, OFFSETS, PULL BOXES AND OBSTRUCTIONS. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO INSTALL THEIR WORK TO CONFORM TO THE STRUCTURE, MAINTAIN HEADROOM AND KEEP OPENINGS AND PASSAGEWAYS CLEAR. REFER TO THE ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS AS REQUIRED.
16. IT IS NOT INTENDED THAT THE PLANS INDICATE ALL CONDUIT ROUTES, PULL BOXES, ETC. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING ACTUAL CONDUIT ROUTING, QUANTITY AND LOCATION OF PULL BOXES WITHIN ACCESSIBLE LOCATIONS.
17. PROVIDE SCREW-COVER PULL BOXES IN CONDUIT RUNS AS REQUIRED TO LIMIT THE NUMBER OF BENDS TO NO MORE THAN THREE (3) OR 270 DEGREES TOTAL. SIZE PULL BOXES IN ACCORDANCE WITH NEC, ARTICLE 314.28. DOCUMENT ON RECORD DRAWINGS, SIZE AND LOCATION OF PULL BOXES USED IN FEEDER CONDUIT RUNS.
18. ALL OUTLET BOXES IN WALLS SHALL HAVE A MINIMUM OF ONE (1) DEDICATED VERTICAL CONDUIT ENTERING AT THE TOP OF THE BOX. HORIZONTAL CONDUIT CONNECTIONS SHALL ONLY BE PERMITTED UNDER WINDOWS OR UNLESS OTHERWISE NOTED ON DRAWINGS.
19. WHERE MULTIPLE DEVICES ARE INDICATED IN A COMMON LOCATION, GANG INTO A SINGLE COVER PLATE.
20. NEW OR MODIFIED PANELS SHALL BE PROVIDED WITH ENGRAVED NAMEPLATES AS DESIGNATED ON PANEL SCHEDULES SECURED TO PANEL FACE AND DENOTING ORIGIN OF FEEDER FROM WHICH PANEL IS SERVED.

SYMBOL LEGEND

SYMBOL	DESCRIPTION
	LUMINAIRE. "A" INDICATES TYPE; "N" INDICATES SWITCH CONTROL. "/EM" INDICATES LUMINAIRE HAS INTEGRAL 90-MINUTE EMERGENCY BATTERY DRIVER.
	LUMINAIRE WIRED FOR 24 HOUR OPERATION, INDICATED WITH HATCH AND A "/N" DESIGNATION.
	SELF CONTAINED LED UNIVERSAL MOUNTED "EXIT" SIGN. PROVIDE QUANTITY OF FACES AND DIRECTIONAL ARROWS AS INDICATED ON FLOOR PLANS. REFER TO LUMINAIRE SCHEDULE FOR ADDITIONAL INFORMATION.
	EMERGENCY LIGHTING BATTERY UNIT WITH HEADS AS INDICATED. REFER TO LUMINAIRE SCHEDULE FOR ADDITIONAL INFORMATION.
	LIGHT SWITCH, SINGLE POLE; 20 AMPERE, 120/277 VOLT, 1HP. "X" INDICATES SWITCH CONTROL. "X" INDICATES THE FOLLOWING: "S" CONTROL OF SPECIFIED LUMINAIRES. "3" THREE-WAY TYPE. "4" FOUR-WAY TYPE. "D" SWITCH TO BE WIRED AHEAD OF DOWNSTREAM LINE VOLTAGE WALLBOX TYPE DIMMING SWITCH, INDICATED BY THE SAME SWITCH CONTROL TAG. "2P" DOUBLE POLE TYPE. "TW" PROGRAMMABLE TIMER SWITCH, TYPICALLY HONEYWELL #RPLS730B. "OS" LINE VOLTAGE MULTI-TECHNOLOGY WALL SWITCH OCCUPANCY SENSOR WITH MANUAL ON/OFF SWITCH. REFER TO DIAGRAM ON DRAWING ### . "VS" LINE VOLTAGE MULTI-TECHNOLOGY WALL SWITCH VACANCY SENSOR WITH MANUAL ON/OFF SWITCH. REFER TO DIAGRAM ON DRAWING ### . "COS" LINE VOLTAGE PIR WALL SWITCH CORRIDOR-TYPE OCCUPANCY SENSOR WITHOUT CONTROL SWITCH, TYPICALLY SENSOR SWITCH #HWR13-SN SERIES. MOUNT AT 7'-0" A.F.F. UNLESS OTHERWISE SHOWN. "CYS" LINE VOLTAGE PIR WALL SWITCH CORRIDOR-TYPE OCCUPANCY SENSOR WITH CONTROL SWITCH, TYPICALLY SENSOR SWITCH #HWR13 SERIES. MOUNT AT 7'-0" A.F.F. UNLESS OTHERWISE SHOWN. "VDS" LINE VOLTAGE ON/OFF SWITCH WITH DIMMER FUNCTION AND VACANCY SENSOR. REFER TO DIAGRAM ON DRAWING ### . "LV" LOW VOLTAGE ON/OFF SWITCH. "LV2" DUAL ZONE LOW VOLTAGE ON/OFF SWITCH. "LV4" QUAD ZONE LOW VOLTAGE ON/OFF SWITCH. "LVD" LOW VOLTAGE ON/OFF SWITCH WITH DIMMER FUNCTION. "LVD2" DUAL ZONE LOW VOLTAGE ON/OFF SWITCH WITH DIMMER FUNCTION. "LVD4" QUAD ZONE LOW VOLTAGE ON/OFF SWITCH WITH DIMMER FUNCTION. "SCN" SCENE CONTROLLER CAPABLE OF A MINIMUM OF FOUR PRESETS.
	LINE VOLTAGE WALLBOX TYPE DIMMING SWITCH. COORDINATE DIMMING PROTOCOL OF THIS DIMMING SWITCH AND LIGHTING LOAD SERVED PRIOR TO PLACING PURCHASE ORDER. "S" INDICATES SWITCH CONTROL.
	120/277V RATED CEILING MOUNTED OCCUPANCY SENSOR. A "DR" DESIGNATIONS INDICATES A DUAL RELAY SENSOR FOR 3/4 WAY SWITCHING. "X" REPRESENTS CONTROLLED LIGHTING ZONE (IF LOCATED IN A ROOM/AREA WITH MULTIPLE LIGHTING ZONES). TYPICALLY SENSOR SWITCH #CMR SERIES.
	LOW VOLTAGE CEILING MOUNTED PHOTOSENSOR, "X" REPRESENTS CONTROLLED LIGHTING ZONE.
	LOW VOLTAGE MULTI-TECHNOLOGY CEILING MOUNTED OCCUPANCY SENSOR, "X" REPRESENTS CONTROLLED LIGHTING ZONE.
	LOW VOLTAGE MULTI-TECHNOLOGY CEILING MOUNTED VACANCY SENSOR, "X" REPRESENTS CONTROLLED LIGHTING ZONE.
	CIRCUITRY TURNING UP
	CIRCUITRY TURNING DOWN
	UNDERGROUND OR UNDERSLAB CONDUIT/RACEWAY AND/OR CIRCUITING.
	CONDUIT HOME RUN TO PANEL/CIRCUIT BREAKER AS INDICATED. ALL UNMARKED HOMERUNS TO CONTAIN 2-12 AWG AND IN 3/4" CONDUIT (MINIMUM), UNLESS NOTED OTHERWISE. SIZE CONDUIT AND PROVIDE JUNCTION BOXES PER CODE UNLESS OTHERWISE NOTED.
	DWELLING UNITS; DWELLING UNIT SINGLE-PHASE LOAD CENTER.
	ALL OTHER AREAS; BRANCH CIRCUIT PANELBOARD.
	DISCONNECT SWITCH. REFER TO EQUIPMENT SCHEDULE OR PLAN NOTE FOR FUSING NECESSITY, SIZES, RATINGS, ETC.
	DUPLEX RECEPTACLE - 125 VOLT, 20 AMPERE, 2 POLE, 3 WIRE, GROUNDING TYPE MOUNTED AT 18" AFF UNLESS NOTED OTHERWISE.
	DOUBLE DUPLEX RECEPTACLE - 125 VOLT, 20 AMPERE, 2 POLE, 3 WIRE, GROUNDING TYPE MOUNTED AT 18" AFF UNLESS NOTED OTHERWISE.
	GFCI GROUND TYPE DUPLEX RECEPTACLE - 125 VOLT, 20 AMPERE, 2 POLE, 3 WIRE, GROUNDING TYPE MOUNTED AT 18" AFF UNLESS NOTED OTHERWISE.
	DUPLEX RECEPTACLE - 125 VOLT, 20 AMPERE, 2 POLE, 3 WIRE, GROUNDING TYPE MOUNTED AT 18" AFF UNLESS NOTED OTHERWISE. RECEPTACLE SHALL BE SPLIT WIRED SUCH THAT TOP OUTLET TO BE WIRED FOR SWITCHING TO SWITCH INDICATED BY 'S'.
	TAMPER RESISTANT, POP-UP COUNTER RECEPTACLE - 125 VOLT, 20 AMPERE, 2 POLE, 3 WIRE, GROUNDING TYPE. TYPICALLY BRYANT #RCT220xx.
	FLOOR BOX WITH DUPLEX RECEPTACLE. PROVIDE APPROPRIATE BOX TYPE FOR CONCRETE OR WOOD FLOOR CONSTRUCTION.
	RECEPTACLE SYMBOL WITH ADDITIONAL SUBSCRIPT DESIGNATES TYPE OR SPECIFIC REQUIREMENTS AS FOLLOWS: "AC" INDICATES MOUNTED 8" ABOVE COUNTER UNLESS NOTED OTHERWISE ON ARCHITECTURAL ELEVATIONS. "CLG" FLUSH CEILING MOUNTED OR 12" ABOVE WINDOW. "AB" RECEPTACLE MOUNTED AT HEIGHT INDICATED. "IL" RECEPTACLE WITH ILLUMINATED NIGHT LIGHT. "VF" VERIFY EXISTING MOUNTING HEIGHT IN FIELD, OR CONFIRM EXACT LOCATION IN OF NEW DEVICE IN FIELD. "WP" WEATHERPROOF "WHILE-IN-USE" (HUBBELL #WP26M) COVER. "U" DUPLEX RECEPTACLE WITH ONE USB TYPE "A" PORT AND ONE TYPE "C" PORT, LEVITON #TS633 SERIES OR EQUAL. "T" TAMPER RESISTANT (ONLY INDICATED OUTSIDE OF DWELLING UNITS). "G" RECEPTACLE PROTECTED BY UPSTREAM GFCI OR GFI-TYPE BREAKER WITH "GFCI PROTECTED" LABEL ON THE FACE OF DEVICE. "CR" RECEPTACLE CONTROLLED BY AN AUTOMATIC CONTROL DEVICE FOR PLUS LOAD CONTROL. DURABLY AND PERMANENTLY MARKED WITH THE WORD "CONTROLLED" AND THE SYMBOL SHOWN IN NEC FIGURE #406.3(F) .
	SPECIAL PURPOSE RECEPTACLE. REFER TO EQUIPMENT SCHEDULE OR PLAN NOTE FOR RECEPTACLE TYPE AND RATINGS. COORDINATE EXACT NEMA CONFIGURATION WITH EQUIPMENT PRIOR TO ROUGH-IN.
	JUNCTION BOX - SIZE PER N.E.C. ARTICLE 314 REQUIREMENTS.
	ALL AREAS, BESIDES IN DWELLING UNITS; COMBINATION VOICE/DATA OUTLET (4" x 2-1/8" DEEP JUNCTION BOX) COMPLETE WITH SINGLE GANG MUD RING (VERIFY DRYWALL THICKNESS) AND COVER PLATE (COLOR SELECTION BY ARCHITECT) MOUNTED AT 18" A.F.F. PROVIDE 1-0" CONDUIT WITH INSULATING BUSHING AND PULLSTRING STUBBED UP 12" INTO ACCESSIBLE CEILING SPACE.
	WITHIN DWELLING UNITS; REFER TO TYPICAL APARTMENT DATA FACEPLATE DETAILS ON DRAWING ### .
	FLOOR BOX WITH DATA/VOICE OUTLET AS DESCRIBED ABOVE. PROVIDE APPROPRIATE BOX TYPE FOR CONCRETE OR WOOD FLOOR CONSTRUCTION.
	FIRE ALARM SYSTEM MANUAL PULL STATION.
	FIRE ALARM COMBINATION AUDIBLE/VISUAL (HORN/STROBE) SIGNALING DEVICE. LF DESIGNATION INDICATES LOW FREQUENCY ALARM DEVICE.
	FIRE ALARM VISUAL (STROBE) ONLY SIGNALING DEVICE.
	ALL AREAS, BESIDES IN DWELLING UNITS; FIRE ALARM SYSTEM SMOKE DETECTOR.
	WITHIN DWELLING UNITS; DWELLING UNIT SMOKE ALARM. REFER TO DETAIL(S) ON DRAWING ### .
	WITHIN DWELLING UNITS; BUILDING FIRE ALARM SYSTEM ADDRESSABLE SMOKE DETECTOR WITH 520HZ LOW FREQUENCY SOUNDER BASE.
	"CO" DESIGNATION INDICATES COMBINATION, "MULTI-CRITERIA" SMOKE/CARBON MONOXIDE CAPABILITY.
	FIRE ALARM CONTROL PANEL. THE BRANCH CIRCUIT SERVING THIS PANEL SHALL ONLY SERVE FIRE ALARM EQUIPMENT. REFER TO PANEL SCHEDULE(S).
	FIRE ALARM ANNUNCIATOR PANEL. THE BRANCH CIRCUIT SERVING THIS PANEL SHALL ONLY SERVE FIRE ALARM EQUIPMENT. REFER TO PANEL SCHEDULE(S).
	TAMPER SWITCH. COORDINATE ALL REQUIREMENTS WITH SPRINKLER/FIRE SUPPRESSION DRAWINGS.
	FLOW SWITCH. COORDINATE ALL REQUIREMENTS WITH SPRINKLER/FIRE SUPPRESSION DRAWINGS.
	MAGNETIC DOOR HOLD OPEN

WIRING SCHEDULE FOR 15/20A RECEPTACLE & LIGHTING CIRCUITS	
DISTANCE	120V
1' - 100'	#12 (AWG)
100' - 150'	#10 (AWG)
150' - 200'	#10 (AWG)
200' - 300'	#8 (AWG)

Seal

NOT FOR CONSTRUCTION

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC

who's
engineering
2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505

OSU
AIRPORT WEST
BUILDING A

3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title
ELECTRICAL LEGEND
AND DETAILS

Date:	Project Number:
03.05.2026	24-065
Drawn By:	Drawing Number:
DJS	
Checked By:	
KDS	
Approved:	
GSS	

E0.03A

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC

DESIGN DEVELOPMENT	03.05.26	BAC
--------------------	----------	-----

--

--	--

2014

engineering

Cleveland, OH 44113

OSU

AIRPORT WEST

3455 W. Dublin Granville Rd,

Drawing Title

AND DETAILS


03.05.2026	24-065
------------	--------

DJS
 Checked by: **FG 04A**

Approved	
GSS	



- A. PROVIDE A COMPLETE, OPERATING TWO-WAY COMMUNICATION SYSTEM CONSISTING OF A **FIRST FLOOR** BASE STATION AND CALL BOX STATION ELEVATOR LANDING LOCATIONS ALL REMAINING FLOORS. SYSTEM SHALL COMPLY WITH ALL STATE CODES. LOCAL CODES AND ADA. MANUFACTURER SHALL BE PATH AREA OF REFUGE" OR EQUIV BY CORNELL.
- B. INSTALL ALL CABLE PER MANUFACTURER'S INSTRUCTIONS. WIRING SHALL BE INSTALLED IN 3/4" CONDUIT (MINIMUM).
- C. COORDINATE LOCATION OF BASE STATION AND CALL BOX STATIONS WITH THE AHJ AND ARCHITECT PRIOR TO ROUGH-IN.
- D. SUBMITTAL SHALL INCLUDE EQUIPMENT DATA SHEETS, OPERATING MANUALS AND DETAILED WIRING SCHEMATICS.
- E. ALL RECESSED BOXES/BASE STATION SHALL BE FIRESTOPPED TO MAINTAIN FIRE RATING OF WALL.




FEEDER SCHEDULE				
ID	NOMINAL AMPACITY	CONDUCTOR & CONDUIT SIZE	CONDUCTOR MATERIAL	NOTES
1	20A	2#10, 1#10(G), 1-1/2" C.	COPPER	1,5
2	155A	4#3/0, 1#4(G), 2" C.	ALUMINUM	1,3
3	310A	4#500KCMIL, 3" C.	ALUMINUM	1,3
4	780A	2 SETS OF 4#750KCMIL, 1#3/0(G), 4" C.	ALUMINUM	1,3
5	1020A	3 SETS OF 4#600KCMIL, 1#4/0(G), 4" C.	ALUMINUM	1,3
6	1700A	5 SETS OF 4#600KCMIL, 4" C.	ALUMINUM	1,2
7	2695A	7 SETS OF 4#750KCMIL, 4" C.	ALUMINUM	1,2
FP1	85A	4#3, 1-1/2" C.	COPPER	1,2,5
FP2	85A	3#3, 1#8(G), 1-1/2" C.	COPPER	1,2,5
GN	85A	4#3, 1#8(G), 1-1/2" C.	COPPER	1,2,5
APT	120A (1&2 BED)	3#1/0, 1#4(G), 1-1/2" C. (1&2 BED)	ALUMINUM	1,3,4
APT	135A (3 BED)	3#2/0, 1#4(G), 2" C. (3 BED)	ALUMINUM	1,3,4
PC	-	TWO EMPTY 5" CONDUITS.	-	6

FEEDER SCHEDULE NOTES:

- ALL CONDUCTORS ARE BASED ON EITHER TYPE "TW"/"UF" (UNDER AND INCLUDING #1AWG) OR TYPE "THHW"/"THHN" (OVER #1AWG) INSULATION WITH A 60°C RATING (UNDER AND INCLUDING #1AWG) OR A 75°C RATING (OVER #1AWG) IN ADDITION TO 75°C TERMINATIONS. CONDUIT SIZES ARE ALSO INDICATED.
- REFER TO RESPECTIVE TRENCH SECTION DETAIL ON SHEET #ES.02A FOR ADDITIONAL INFORMATION REGARDING THIS FEEDER.
- COPPER CONDUCTORS MAY BE UTILIZED FOR THIS FEEDER. HOWEVER, THE E.C. IS RESPONSIBLE FOR PROVIDING THE APPROPRIATE CONDUCTOR SIZE IN ACCORDANCE WITH N.E.C. TABLE #310.15(B)(16).
- TYPE SER CABLE FOR MAY BE UTILIZED FOR THIS FEEDER IN LIEU OF CONDUCTORS IN CONDUIT.
- THIS FEEDER IS SIZED TO ACCOUNT FOR VOLTAGE DROP (ALL FEEDS WITH THIS NOTE) AND SHARED CONDUIT DERATING FACTOR (FOR FEEDER #1).
- ROUTE TWO 5" CONDUITS TO LOCATION DETERMINED BY LOCAL UTILITY COMPANY.

CODED NOTES

- PROVIDE A U.L. LISTED, 1200A METER CENTER TAPBOX RATED AT **208/120V-3ø-4W**, TYPICALLY SIEMENS #WTB SERIES. ENTIRE ASSEMBLY SHALL BE RATED AT A MINIMUM **65,000 RMS** SYMMETRICAL SHORT CIRCUIT AMPERES. ACCEPTABLE ALTERNATIVES SHALL BE Eaton, SQUARE D, OR GENERAL ELECTRIC, HOWEVER, THE E.C. SHALL BE RESPONSIBLE FOR ENSURING MODIFIED EQUIPMENT, SIZES, ETC. MEET N.E.C. CLEARANCE CRITERIA.
- PROVIDE RESIDENTIAL METER STACK (QUANTITY AS INDICATED) WITH THREE PHASE HORIZONTAL BUS (CAPACITY AS SHOWN) AND BOLT-ON CIRCUIT BREAKERS, TYPICALLY SIEMENS #MMW SERIES. APPROXIMATE DIMENSIONS ARE 16.22"W X 43.31"H X 8.09"D (3 METER STACK) AND 16.22"W X 70.31"H X 8.09"D (6 METER STACK). ACCEPTABLE ALTERNATIVES SHALL BE Eaton, SQUARE D, OR GENERAL ELECTRIC, HOWEVER, THE E.C. SHALL BE RESPONSIBLE FOR ENSURING MODIFIED EQUIPMENT, SIZES, ETC. MEET N.E.C. CLEARANCE CRITERIA. METER STACK SHALL BE PROVIDED SUCH THAT NO CIRCUIT BREAKER SHALL EXCEED 6'-8" A.F.F. PROVIDE ALL REQUIRED HOUSEKEEPING PADS IN FRONT OF EQUIPMENT TO MEET THIS REQUIREMENT. COORDINATE ALL METER SOCKET REQUIREMENTS WITH LOCAL UTILITY COMPANY. ENTIRE ENCLOSURE SHALL BE RATED AT A MINIMUM **65,000 RMS** SYMMETRICAL SHORT CIRCUIT AMPERES.
- LOCATION OF 125A-2P (ONE AND TWO BEDROOM APARTMENT UNITS) AND 150A-2P (THREE BEDROOM APARTMENT UNITS) TENANT MAIN CIRCUIT BREAKER TO BE PROVIDED WITH METER STACK. REFER TO UNIT LOAD CALCULATIONS ON DRAWING #E3.00C. ALL MAIN CIRCUIT BREAKERS SHALL BE RATED AT A MINIMUM **100,000 RMS** SYMMETRICAL SHORT CIRCUIT AMPERES.
- PROVIDE A U.L. LISTED "SERVICE ENTRANCE RATED" (RATINGS AS INDICATED ON RISER) DISTRIBUTION SWITCHBOARD, TYPICALLY SIEMENS #S82 SERIES. ASSEMBLY SHALL BE RATED AT A MINIMUM 100,000 RMS SYMMETRICAL SHORT CIRCUIT AMPERES. SWITCHBOARD SHALL INCLUDE ANY SECTION/PROVISIONS FOR UTILITY COMPANY METERING COMPLYING WITH LOCAL UTILITY COMPANY REQUIREMENTS AND SHALL INCLUDE A SIEMENS #TPS4-06 SERIES SURGE PROTECTION DEVICE OR EQUAL BY OTHERS, AND A #PAC4220 METERING/MONITORING DEVICE. PROVIDE CONCRETE PAD IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- TYPICAL GUEST SUITE LOAD CENTER "GSX", TYPICALLY SIEMENS #ES SERIES. REFER TO TYPICAL PANEL SCHEDULES ON DRAWING #E3.00C FOR GUEST UNIT SERVICE CALCULATIONS, PANEL SIZES AND BREAKERS, AND OTHER ADDITIONAL INFORMATION. PROVIDE A TYPE 2 SURGE PROTECTIVE DEVICE (SPD) AND INSTALL IN EACH LOAD CENTER IN ACCORDANCE WITH NEC #215.18, TYPICALLY SIEMENS #QSPD-2-A-065 OR EQUAL BY OTHERS. THE KAIC RATING OF THE SPD SHALL NOT BE LESS THAN THE RATING OF THE LOAD CENTER AS SHOWN ON THE PANEL SCHEDULE.
- PROVIDE ARC FAULT REDUCTION IN ACCORDANCE WITH N.E.C. ARTICLE #240.87.
- CAM LOCK CONNECTION FOR REDUNDANT TEMPORARY MAINTENANCE GENERATOR LOCATED ON MANUAL TRANSFER SWITCH.
- PRIOR TO ORDERING EQUIPMENT, PROVIDE SELECTIVE COORDINATION STUDY FOR EMERGENCY SYSTEM PER NEC #700.32. CIRCUIT BREAKERS IN PANEL SHALL BE COORDINATED WITH ALL UPSTREAM OVERCURRENT PROTECTION DEVICES.
- THE EMERGENCY STANDBY GENERATOR MUST BE U.L. LISTED IN ACCORDANCE WITH U.L. #2200. PROVIDE A **20A-120V-1ø** BRANCH CIRCUIT FOR SERVICE TO BATTERY CHARGER AND A **20A-120V-1ø** BRANCH CIRCUIT FOR SERVICE TO GENERATOR BLOCK HEATER. CONNECT PER MANUFACTURER'S WIRING DIAGRAM.
- PROVIDE ALL EQUIPMENT, ACCESSORIES, WIRING, ETC. IN COMPLIANCE WITH N.E.C. ARTICLE #700.3(F). THIS SHALL INCLUDE, BUT, NOT BE LIMITED TO THE PROVISION OF A PERMANENT SWITCHING MEANS TO CONNECT TO A PORTABLE/TEMPORARY GENERATOR, MECHANICAL/ELECTRICAL INTERLOCKING FOR THE PREVENTION OF INADVERTENT INTERCONNECTION OF POWER SOURCES, CONTACT POINTS THAT ANNUNCIATE AT A LOCATION REMOTE FROM THE GENERATOR, ETC. VERIFY LOCATION WITH ARCHITECT, OWNER, AND GENERATOR MANUFACTURER.
- PROVIDE A 400A-3P, 240V RATED, SERVICE ENTRANCE RATED, FUSED DISCONNECT SWITCH, FUSED AT **400A**. DISCONNECT SHALL BE INSTALLED IN ACCORDANCE WITH NEC #695.4(D).
- PROVIDE A 100A, 240V, 4W SELF CONTAINED UTILITY METER SOCKET. COORDINATE PROVISION AND WORK REGARDING UTILITY METER WITH LOCAL UTILITY COMPANY.
- PROVIDE A 320A, 240V, 4W SELF CONTAINED UTILITY METER SOCKET. COORDINATE PROVISION AND WORK REGARDING UTILITY METER WITH LOCAL UTILITY COMPANY.
- ROUTE TO THE FIRE CONTROL PANEL FOR THE 20HP FIRE PUMP WITH INTEGRAL AUTOMATIC TRANSFER SWITCHING CAPABILITY AND SOFT START METHOD TO BE SUPPLIED BY THE PLUMBING AND/OR FIRE SUPPRESSION CONTRACTOR. ALL WIRING TO BE PROVIDED BY THE E.C. INCLUDE ALL WIRING REQUIRED FOR A COMPLETE ELECTRICAL INSTALLATION IN ACCORDANCE WITH THE MANUFACTURER'S REQUIREMENTS, IN ADDITION TO STATE AND LOCAL CODES. THE INSTALLATION SHALL BE IN FULL COMPLIANCE WITH WITH N.E.C. ARTICLE #695.
- PROVIDE CONCRETE PAD OR PRE-CAST CONCRETE VAULT IN ACCORDANCE WITH UTILITY COMPANY REQUIREMENTS. ADDITIONALLY, PROVIDE A TRANSFORMER GROUNDING MAT IN ACCORDANCE WITH UTILITY COMPANY REQUIREMENTS.
- ROUTE A #3/0 COPPER GROUND CONDUCTOR TO THE GROUND BUS BAR DESCRIBED IN CODED NOTE #16.
- PROVIDE A MASTER SERVICE ENTRANCE GROUND BUS TO WHICH ALL SERVICE ENTRANCE MAINS SHALL BE BONDED. TYPICAL EQUIPMENT SHALL BE A STORM COPPER #SCBG-6KT GROUND BAR KIT. BAR SHALL BE .25" THICK, 4" X 12" BAR MOUNTED ON (2) BRACKETS W/INSULATORS. PROVIDE A MINIMUM OF (6) .437" DIAMETER 2-HOLE AND (6) .281" DIAMETER MOUNTINGS OR AS OTHERWISE REQUIRED.



Seal

NOT FOR
CONSTRUCTION

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC

whs
engineering
2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**

3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title
POWER RISER DIAGRAM

Date	Project Number
03.05.2026	24-065
Drawn By DJS	Drawing Number
Checked By KDS	E0.05A
Approved GSS	

METER CENTER "MC-ASW3" ELECTRIC SERVICE CALCULATION					
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE
1 BEDROOM UNIT					
1BED UNIT TYPE A1	713	2	3	4278	220.84(c)(1)
1BED UNIT TYPE AD2	897	4	3	10764	220.84(c)(1)
1BED UNIT TYPE AD2 PW	897	4	3	10764	220.84(c)(1)
1BED UNIT TYPE S1	704	6	3	12672	220.84(c)(1)
2 BEDROOM UNIT					
2BED UNIT TYPE B1.2	1035	2	3	6210	220.84(c)(1)
2BED UNIT TYPE BD3.1	1275	2	3	7650	220.84(c)(1)
3 BEDROOM UNIT					
3BED UNIT TYPE C3	1442	2	3	8652	220.84(c)(1)
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD:				60,990 W	
SMALL APPLIANCE BRANCH CIRCUITS	-	44	1500	66000	220.84(c)(2)
1 LAUNDRY CIRCUIT (WASHING MACHINE)	-	22	1500	33000	220.84(c)(2)
REFRIGERATOR	-	22	600	13200	220.84(c)(3)
ELECTRIC RANGE/OVEN	-	22	8000	176000	220.84(c)(3)
RANGE HOOD/MICROWAVE	-	22	1680	36960	220.84(c)(3)
DISHWASHER/DISPOSER	-	22	1200	26400	220.84(c)(3)
ELECTRIC DRYER	-	22	5000	110000	220.84(c)(3)
ELECTRIC WATER HEATER	-	22	4500	99000	220.84(c)(5)
1.5 TON HVAC	-	16	5180	82880	220.84(c)(5)
2 TON HVAC	-	4	6698	26792	220.84(c)(5)
2.5 TON HVAC	-	2	8871	17742	220.84(c)(5)
TOTAL CONNECTED EQUIPMENT LOAD:				68,974 W	
TOTAL CONNECTED LOAD:				748,964 W	
DEMAND FACTOR:				36%	TABLE 220.84
TOTAL DEMAND LOAD:				269,627 W	
AMPS AT 120V/208V-3Ø				748.4 A	

METER CENTER "MC-A5E2" ELECTRIC SERVICE CALCULATION						
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE	
1 BEDROOM UNITS						
1BED UNIT TYPE A1	713	8	3	17112	220.84(c)(1)	
1BED UNIT TYPE AD2	897	4	3	10784	220.84(c)(1)	
1BED UNIT TYPE AD2 PW	897	4	3	10784	220.84(c)(1)	
1BED UNIT TYPE S1	704	6	3	12972	220.84(c)(1)	
2 BEDROOM UNITS						
2BED UNIT TYPE B1	1035	3	3	9315	220.84(c)(1)	
2BED UNIT TYPE B1.3	1062	1	3	3188	220.84(c)(1)	
2BED UNIT TYPE B03.1	1275	2	3	7650	220.84(c)(1)	
3 BEDROOM UNITS						
3BED UNIT TYPE C3	1442	2	3	8652	220.84(c)(1)	
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD:				80,115 W		
SMALL APPLIANCE BRANCH CIRCUITS						
LAUNDRY CIRCUIT (WASHING MACHINE)	-	60	1500	90000	220.84(c)(2)	
REFRIGERATOR	-	30	1500	45000	220.84(c)(2)	
ELECTRIC RADIATOR	-	8000	8000	18000	220.84(c)(3)	
RANGE HOOD/MICROWAVE	-	30	1680	50400	220.84(c)(3)	
DISHWASHER/DISPOSER	-	30	1200	36000	220.84(c)(3)	
ELECTRIC DRYER	-	30	5000	150000	220.84(c)(3)	
ELECTRIC WATER HEATER	-	20	4500	135000	220.84(c)(3)	
1.5 TON HVAC	-	22	5180	113960	220.84(c)(5)	
2 TON HVAC	-	6	6668	40188	220.84(c)(5)	
2.5 TON HVAC	-	2	8871	17742	220.84(c)(5)	
TOTAL CONNECTED EQUIPMENT LOAD:				936,290 W		
TOTAL CONNECTED LOAD:				1,016,405 W		
DEMAND FACTOR:				33%	TABLE 220.84	
TOTAL D.A. W				335,414 W		
AMPS AT 120/208V-3Ø						

APARTMENT SWITCHBOARD "ASWB-A" ELECTRIC SERVICE CALCULATION						
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE	
1 BEDROOM UNITS						
1BED UNIT TYPE A1	713	16	3	34224	220.84(c)(1)	
1BED UNIT TYPE AD3	1025	1	3	3075	220.84(c)(1)	
1BED UNIT TYPE AD2 PW	897	8	3	21528	220.84(c)(1)	
1BED UNIT TYPE S1	897	8	3	21528	220.84(c)(1)	
1BED UNIT TYPE S1	704	12	3	25344	220.84(c)(1)	
2 BEDROOM UNITS						
2BED UNIT TYPE B1	1035	7	3	21735	220.84(c)(1)	
2BED UNIT TYPE B1.2	1035	4	3	12420	220.84(c)(1)	
2BED UNIT TYPE BD3.2	1035	4	3	11475	220.84(c)(1)	
2BED UNIT TYPE B1.1	1035	4	3	12420	220.84(c)(1)	
2BED UNIT TYPE BD3.1	1275	4	3	15300	220.84(c)(1)	
3 BEDROOM UNITS						
3BED UNIT TYPE C3	1062	8	3	25488	220.84(c)(1)	
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD				204,587		
SMALL APPLIANCE BRANCH CIRCUITS						
LAUNDRY CIRCUIT (WASHING MACHINE)	-	150	1500	225000	220.84(c)(2)	
REFRIGERATOR	-	75	1500	112500	220.84(c)(2)	
ELECTRIC RANGE/OVEN	-	75	8000	600000	220.84(c)(3)	
ELECTRIC DISHWASHER	-	75	1600	120000	220.84(c)(3)	
DISHWASHER/DISPOSER	-	75	1200	90000	220.84(c)(3)	
ELECTRIC DRYER	-	75	5000	375000	220.84(c)(3)	
ELECTRIC WATER HEATER	-	75	4500	337500	220.84(c)(3)	
1.5 TON HVAC	-	45	5180	233100	220.84(c)(5)	
2.0 TON HVAC	-	19	5698	127262	220.84(c)(5)	
2.5 TON HVAC	-	8	8871	79968	220.84(c)(5)	
TOTAL CONNECTED EQUIPMENT LOAD:				2,342,330		
TOTAL CONNECTED LOAD:				2,546,887		
DEMAND FACTOR:				23%	TABLE 220.84	
TOTAL DEMAND LOAD:				565,778		
AMPS AT 120/208V-3Ø			1,626.0 A			

APARTMENT SWITCHBOARD "ASWB-B" ELECTRIC SERVICE CALCULATION						
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE	
1 BEDROOM UNITS						
1BED UNIT TYPE A1	713	27	3	57753	220.84(c)(1)	
1BED UNIT TYPE A1.1	709	3	3	6381	220.84(c)(1)	
1BED UNIT TYPE A1.2	709	3	3	6381	220.84(c)(1)	
1BED UNIT TYPE A2	897	8	3	21528	220.84(c)(1)	
1BED UNIT TYPE A2 PW	897	8	3	21528	220.84(c)(1)	
1BED UNIT TYPE S1	704	12	3	25344	220.84(c)(1)	
2 BEDROOM UNITS						
2BED UNIT TYPE B1	1035	13	3	40395	220.84(c)(1)	
2BED UNIT TYPE B1.1	1035	3	3	9515	220.84(c)(1)	
2BED UNIT TYPE B1.3	1062	1	3	3186	220.84(c)(1)	
2BED UNIT TYPE BD3.1	1275	4	3	15300	220.84(c)(1)	
2BED UNIT TYPE B1A	1035	1	3	3105	220.84(c)(1)	
2BED UNIT TYPE BD3.2	1275	4	3	15300	220.84(c)(1)	
3 BEDROOM UNITS						
3BED UNIT TYPE C3	1445	8	3	34580	220.84(c)(1)	
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD				280,166 W		
SMALL APPLIANCE BRANCH CIRCUITS	-	190	1500	285000	220.84(c)(2)	
LAUNDRY CIRCUIT (WASHING MACHINE)	-	95	1500	142500	220.84(c)(2)	
REFRIGERATOR	-	95	800	57000	220.84(c)(3)	
ELECTRIC RANGE	-	95	8000	220000	220.84(c)(3)	
FREEZE HOOD/CROKVAPE	-	95	1680	159600	220.84(c)(3)	
DISHWASHER/DISPOSER	-	95	1200	114000	220.84(c)(3)	
ELECTRIC DRYER	-	95	5000	475000	220.84(c)(3)	
ELECTRIC WATER HEATER	-	95	4500	427500	220.84(c)(3)	
1.5 TON HVAC	-	61	5160	313800	220.84(c)(5)	
2 TON HVAC	-	21	6998	140658	220.84(c)(5)	
2.5 TON HVAC	-	8	8871	70668	220.84(c)(5)	
TOTAL CONNECTED EQUIPMENT LOAD:				2,948,206 W		
TOTAL CONNECTED LOAD:				3,208,372 W		
DEMAND FACTOR:				23%	TABLE 220.84	
TOTAL DEMAND LOAD:				737,928 W		
AMPS AT 120/208V-3Ø				2,048.3 A		

METER CENTER "MC-ASW1" ELECTRIC SERVICE CALCULATION					
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE
1 BEDROOM UNITS					
1BED UNIT TYPE A1	713	2	3	4278	220.84(c)(1)
1BED UNIT TYPE AD2	897	4	3	10784	220.84(c)(1)
1BED UNIT TYPE AD2 PW	897	4	3	10784	220.84(c)(1)
1BED UNIT TYPE S1	704	6	3	12672	220.84(c)(1)
2 BEDROOM UNITS					
2BED UNIT TYPE B1.2	1035	2	3	6210	220.84(c)(1)
2BED UNIT TYPE BD3.1	1275	2	3	7650	220.84(c)(1)
3 BEDROOM UNITS					
3BED UNIT TYPE C3	1442	2	3	8652	220.84(c)(1)
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD:				60,990 W	
SMALL APPLIANCE BRANCH CIRCUITS	-	44	1500	95000	220.84(c)(2)
1 LAUNDRY CIRCUIT (WASHING MACHINE)	-	22	1500	33000	220.84(c)(2)
REFRIGERATOR	-	22	600	13200	220.84(c)(2)
ELECTRIC RANGE/OVEN	-	22	8000	176000	220.84(c)(3)
RANGE HOOD/MICROWAVE	-	22	1680	36960	220.84(c)(3)
DISHWASHER/DISPOSER	-	22	1200	26400	220.84(c)(3)
ELECTRIC DRYER	-	22	5000	110000	220.84(c)(3)
ELECTRIC WATER HEATER	-	22	4500	99000	220.84(c)(3)
1.5 TON HVAC	-	16	5160	82880	220.84(c)(5)
2 TON HVAC	-	4	6698	26792	220.84(c)(5)
2.5 TON HVAC	-	2	8871	17742	220.84(c)(5)
TOTAL CONNECTED EQUIPMENT LOAD:				687,974 W	
TOTAL CONNECTED LOAD:				748,964 W	
DEMAND FACTOR:				96%	TABLE 220.84
TOTAL DEMAND LOAD:				289,627 W	
AMPS AT 120/208V-3Ø				748.4 A	

METER CENTER "MC-ASE4" ELECTRIC SERVICE CALCULATION					
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE
1 BEDROOM UNITS					
1BED UNIT TYPE A1	713	6	3	12834	220.84(c)(1)
1BED UNIT TYPE A1.1	709	1	3	2127	220.84(c)
1BED UNIT TYPE A1.2	709	1	3	2127	220.84(c)
1BED UNIT TYPE A2	897	2	3	5382	220.84(c)(1)
1BED UNIT TYPE A2D PW	897	2	3	5382	220.84(c)(1)
1BED UNIT TYPE S1	704	3	3	6336	220.84(c)(1)
2 BEDROOM UNITS					
2BED UNIT TYPE B1	1035	2	3	6210	220.84(c)(1)
2BED UNIT TYPE BD3.1	1275	1	3	3825	220.84(c)(1)
3 BEDROOM UNITS					
3BED UNIT TYPE C3	1492	1	3	4476	220.84(c)(1)
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD				48,698 W	
SMALL APPLIANCE BRANCH CIRCUITS	-	36	1500	5700	220.84(c)(2)
LAUNDRY CIRCUIT (WASHING MACHINE)	-	36	1500	28500	220.84(c)(2)
REFRIGERATOR	-	19	600	11400	220.84(c)(3)
ELECTRIC RANGE/OVEN	-	19	8000	152000	220.84(c)(3)
RANGE HOOD/MICROWAVE	-	19	1680	21920	220.84(c)(3)
DISHWASHER/DISPOSER	-	19	1200	22800	220.84(c)(3)
ELECTRIC DRYER	-	19	5500	95000	220.84(c)(3)
ELECTRIC WATER HEATER	-	19	4500	85500	220.84(c)(3)
1.5 TON HVAC	-	15	5180	77700	220.84(c)(5)
2 TON HVAC	-	3	6688	20064	220.84(c)(5)
2.5 TON HVAC	-	1	8871	8871	220.84(c)(5)
TOTAL CONNECTED EQUIPMENT LOAD				500,785 W	
TOTAL CONNECTED LOAD				630,484 W	
DEMAND FACTOR:				38%	TABLE 220.84
TOTAL DEMAND LOAD				243,904 W	
AMPS AT 120/208V-50				674.5 A	

METER CENTER "MC-A" TOTAL ELECTRIC SERVICE CALCULATION						
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE	
1 BEDROOM UNITS						
1BED UNIT TYPE A1	713	5	3	10695	220.84(c)(1)	
2 BEDROOM UNITS						
2BED UNIT TYPE B1	1035	5	3	15525	220.84(c)(1)	
2BED UNIT TYPE B1.1	1035	3	3	9315	220.84(c)(1)	
2BED UNIT TYPE B1A	1035	1	3	3105	220.84(c)(1)	
2BED UNIT TYPE BD3.2	1275	4	3	15300	220.84(c)(1)	
3 BEDROOM UNITS						
3BED UNIT TYPE C3	1445	4	3	17340	220.84(c)(1)	
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD:				71,250 W		
SMALL APPLIANCE BRANCH CIRCUITS	-	44	1500	66000	220.84(c)(2)	
LAUNDRY CIRCUIT (WASHING MACHINE)	-	22	1500	33000	220.84(c)(2)	
REFRIGERATOR	-	22	600	13200	220.84(c)(3)	
ELECTRIC RANGE/OVEN	-	22	8000	176000	220.84(c)(3)	
RANGE Hood/MICROWAVE	-	22	1600	35200	220.84(c)(3)	
DISHWASHER/DISPOSER	-	22	1200	26400	220.84(c)(3)	
ELECTRIC DRYER	-	22	5000	110000	220.84(c)(3)	
ELECTRIC WATER HEATER	-	22	4500	99000	220.84(c)(3)	
1.5 TON HVAC	-	5	5180	25900	220.84(c)(5)	
2.0 TON HVAC	-	13	6688	87074	220.84(c)(5)	
2.5 TON HVAC	-	4	8871	35484	220.84(c)(5)	
TOTAL CONNECTED EQUIPMENT LOAD:				709,018 W		
TOTAL CONNECTED LOAD:				780,268 W		
DEMAND FACTOR:				36%	TABLE 220.84	
TOTAL DEMAND LOAD:				289,897 W		
AMPS AT 120/208V-3Ø				779.7 A		

METER CENTER "MC-A3E3" ELECTRICAL SERVICE CALCULATION					
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE
1 BEDROOM UNITS					
1BED UNIT TYPE A1	713	8	3	17112	220.84(c)(1)
1BED UNIT TYPE A1.1	709	2	3	4254	220.84(c)(1)
1BED UNIT TYPE A1.2	709	2	3	4254	220.84(c)(1)
1BED UNIT TYPE A2D	897	2	3	5382	220.84(c)(1)
1BED UNIT TYPE A2D PW	897	2	3	5382	220.84(c)(1)
1BED UNIT TYPE S1	704	3	3	6336	220.84(c)(1)
2 BEDROOM UNITS					
2BED UNIT TYPE B1	1035	3	3	9315	220.84(c)(1)
2BED UNIT TYPE B03.1	1275	1	3	3825	220.84(c)(1)
3 BEDROOM UNITS					
3BED UNIT TYPE C3	1442	1	3	4326	220.84(c)(1)
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD				66,186 W	
SMALL APPLANCE BRANCH CIRCUITS		40	1500	72000	220.84(c)(2)
LAUNDRY CIRCUIT (WASHING MACHINE)		24	1500	36000	220.84(c)(2)
REFRIGERATOR		24	600	14400	220.84(c)(3)
ELECTRIC RANGE/OVEN		24	8000	192000	220.84(c)(3)
FREEZER HOODING/CROSKOVE		24	1680	40320	220.84(c)(3)
DISHWASHER/DISPOSER		24	1200	28800	220.84(c)(3)
ELECTRIC DRYER		24	5000	120000	220.84(c)(3)
ELECTRIC WATER HEATER		24	4500	108000	220.84(c)(3)
1.5 TON HVAC		19	5180	98420	220.84(c)(5)
2 TON HVAC		4	6858	27452	220.84(c)(5)
2.5 TON HVAC		1	8871	8871	220.84(c)(5)
TOTAL CONNECTED EQUIPMENT LOAD				745,603 W	
TOTAL CONNECTED LOAD:				805,789 W	
DEMAND FACTOR:				35%	TABLE 220.84
TOTAL DEMAND LOAD:				282,028 W	
AMPS AT 120/208V-3Ø				782.8 A	

METER CENTER "MC-ANW" ELECTRIC SERVICE CALCULATION						
DESCRIPTION	AREA	QUANTITY	LOAD	TOTAL WC	N.E.C. ARTICLE	
1 BEDROOM UNITS						
1BED UNIT TYPE A1	713	12	3	25668	220.84(c)(1)	
1BED UNIT TYPE A03	1025	1	3	3075	220.84(c)(1)	
2 BEDROOM UNITS						
2BED UNIT TYPE B1	1035	7	3	21735	220.84(c)(1)	
2BED UNIT TYPE B1.1	1035	4	3	12420	220.84(c)(1)	
2BED UNIT TYPE B03.2	1275	3	3	11475	220.84(c)(1)	
3 BEDROOM UNITS						
3BED UNIT TYPE C3	1442	4	3	17304	220.84(c)(1)	
TOTAL CONNECTED LIGHTING/RECEPTACLE LOAD:				91,817.50		
SMALL APPLIANCE BRANCH CIRCUITS	-	62	1500	93000	220.84(c)(2)	
LAUNDRY CIRCUIT (WASHING MACHINE)	-	31	1500	45000	220.84(c)(2)	
REFRIGERATOR	-	31	600	18600	220.84(c)(3)	
ELECTRIC RANGE/OVEN	-	31	8000	248000	220.84(c)(3)	
RANGE HOOD/MICROWAVE	-	31	1800	52200	220.84(c)(3)	
DISHWASHER/DISPOSER	-	31	1200	37200	220.84(c)(3)	
ELECTRIC DRYER	-	31	5000	155000	220.84(c)(3)	
ELECTRIC WATER HEATER	-	31	4500	139500	220.84(c)(3)	
1.5 TON HVAC	-	13	5180	67340	220.84(c)(5)	
2 TON HVAC	-	14	6688	93772	220.84(c)(5)	
2.5 TON HVAC	-	4	8871	35484	220.84(c)(5)	
TOTAL CONNECTED EQUIPMENT LOAD:				986,476		
TOTAL CONNECTED LOAD:				1,078,153 W		
DEMAND FACTOR:				32%	TABLE 220.84	
TOTAL DEMAND LOAD:				345,099 W		
AMPS AT 120/208V-3Ø				957.07		


Seal

**NOT FOR
CONSTRUCTION**

Issue: _____ Date: _____ By: _____

SCHEMATIC DESIGN	01.07.26	BAC
------------------	----------	-----

DESIGN DEVELOPMENT	03.05.26	BAC
--------------------	----------	-----



- GENERAL LIGHTING PLAN NOTES
- ALL EXIT SIGNS, EMERGENCY LIGHTING BATTERY PACKS, EMERGENCY LUMINAIRES AND NIGHT LIGHTS (DENOTED "NL") SHALL BE CONNECTED TO THE LOCAL LIGHTING CIRCUIT AHEAD OF ANY CONTROLS SUCH AS: SWITCHES (DEVICE), OCCUPANCY SENSORS AND/OR RELAY CONTROLS.
 - EXACT LOCATION OF ALL LUMINAIRES, AND EXACT MOUNTING HEIGHT OF ALL PENDANT MOUNTED LUMINAIRES SHALL BE COORDINATED WITH ARCHITECTURAL DRAWINGS PRIOR TO ANY ROUGH-INS.
 - REFER TO WIRING SCHEDULE ON SHEET #E0.03A/B/C FOR 15A/20A LIGHTING BRANCH CIRCUITS FOR ALL CONDUCTOR SIZES TO ACCOUNT FOR VOLTAGE DROP.
 - ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN ALL CABINETS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
 - A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

NOT FOR
CONSTRUCTION

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC

who
engineering
2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**

3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title
**FIRST FLOOR LIGHTING
PLAN**

Date:	Project Number:
03.05.2026	24-065
Drawn By:	Drawing Number:
DJS	
Checked By:	
KDS	
Approved:	
GSS	

E1.01A


1
E1.01A
BUILDING A
FIRST FLOOR LIGHTING PLAN
SCALE: 3/32" = 1'-0"



- ALL EXIT SIGNS, EMERGENCY LIGHTING BATTERY PACKS, EMERGENCY LUMINAIRES AND NIGHT LIGHTS (DETONED "N") SHALL BE CONNECTED TO THE LOCAL LIGHTING CIRCUIT AHEAD OF ANY CONTROLS SUCH AS: SWITCHES (DEVICE), OCCUPANCY SENSORS AND/OR RELAY CONTROLS.
- EXACT LOCATION OF ALL LUMINAIRES, AND EXACT MOUNTING HEIGHT OF ALL PENDANT MOUNTED LUMINAIRES SHALL BE COORDINATED WITH ARCHITECTURAL DRAWINGS PRIOR TO ANY ROUGH-IN.
- REFER TO WIRING SCHEDULE ON SHEET **#E03A/B/C** FOR 15A/20A LIGHTING BRANCH CIRCUITS FOR ALL CONDUCTOR SIZES TO ACCORD FOR VOLTAGE DROP.
- ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN PENDING JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPICE OR TERMINATION POINTS, ETC.
- A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE COVER OF ASSOCIATED PANELS.

**NOT FOR
CONSTRUCTION**

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC



**OSU
AIRPORT WEST
BUILDING A**

3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title

**SECOND FLOOR LIGHTING
PLAN**

Date	Project Number
03.05.2026	24-065
Drawn by	Drawing Number
DJS	E1.02A
Checked by	
KDS	
Approved	
GSS	



- NOT FOR
CONSTRUCTION**


whs
engineering

2012 West 25th Street, Suite 90
Cleveland, OH 44113
Phone: 216 227 8505

**3455 W. Dublin Granville Rd,
Columbus OH, 43235**

THIRD FLOOR LIGHTING PLAN

Date 03.05.2026	Project Number 24-065
Drawn by DJS	Drawing Number E1.03A
Checked by KDS	
Approved GSS	



- GENERAL LIGHTING PLAN NOTES
- ALL EXIT SIGNS, EMERGENCY LIGHTING BATTERY PACKS, EMERGENCY LUMINAIRES AND NIGHT LIGHTS (DENOTED "NL") SHALL BE CONNECTED TO THE LOCAL LIGHTING CIRCUIT AHEAD OF ANY CONTROLS SUCH AS: SWITCHES (DEVICE), OCCUPANCY SENSORS AND/OR RELAY CONTROLS.
 - EXACT LOCATION OF ALL LUMINAIRES, AND EXACT MOUNTING HEIGHT OF ALL PENDANT MOUNTED LUMINAIRES SHALL BE COORDINATED WITH ARCHITECTURAL DRAWINGS PRIOR TO ANY ROUGH-INS.
 - REFER TO WIRING SCHEDULE ON SHEET #E0.034/B/C FOR 15A/20A LIGHTING BRANCH CIRCUITS FOR ALL CONDUCTOR SIZES TO ACCOUNT FOR VOLTAGE DROP.
 - ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN ALL CABINETS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
 - A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

Seal

NOT FOR
CONSTRUCTION

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC

who
engineering
2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**


3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title
**FOURTH FLOOR LIGHTING
PLAN**

Date:	Project Number:
03.05.2026	24-065
Drawn By:	Drawing Number:
DJS	
Checked By:	
KDS	
Approved:	
GSS	

E1.04A

1
E1.04A
BUILDING A
FOURTH FLOOR LIGHTING PLAN
SCALE: 3/32" = 1'-0"



- GENERAL POWER AND COMMUNICATION PLAN NOTES
- EXACT LOCATION OF MECHANICAL, PLUMBING, KITCHEN, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT, ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THE MECHANICAL, PLUMBING, AND/OR ARCHITECTURAL DRAWINGS. COORDINATE EXACT LOCATIONS WITH RESPECTIVE CONTRACTORS AND/OR VENDORS PRIOR TO ANY ROUGH-INS.
 - PRIOR TO ROUGH-IN, REVIEW AND COORDINATE WITH ALL OTHER TRADES' CONTRACT DOCUMENTS TO DETERMINE SPECIFIC MOUNTING LOCATIONS AND ELECTRICAL REQUIREMENTS (VOLTAGE, PHASE, KW, HP, CONNECTION TYPE, ETC.) FOR HVAC AND PLUMBING EQUIPMENT. COORDINATE EXACT MOUNTING LOCATIONS WITH THE SPECIFIC TRADE AND ARCHITECT.
 - REFER TO WIRING SCHEDULE ON SHEET **E2.01A/B/C** FOR 15A/20A RECEPTACLE BRANCH CIRCUITS FOR ALL CONDUCTOR SIZES TO ACCOUNT FOR VOLTAGE DROP.
 - ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN ALL CABINETS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
 - A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

- CODED NOTES
- LOCATION OF AREA OF RESCUE COMMUNICATION BASE STATION. REFER TO DIAGRAM ON DRAWING #E0-02.
 - REFER TO ELEVATOR GENERAL INSTALLATION NOTES ON DRAWING #E0-03 FOR ALL ELEVATOR ROOM AND ELEVATOR PIT ELECTRICAL REQUIREMENTS.
 - PROVIDE A 4' x 4' x 3/4" THICK PLYWOOD BACKBOARD PAINTED WITH FIRE RETARDANT PAINT FOR MAIN COMMUNICATION TERMINAL BOARD (TELEPHONE, TELEVISION, ETC.). INCLUDE ALL WORK REQUIRED BY RESPECTIVE UTILITIES. PROVIDE A COPPER GROUNDING BUS AND #6 AWG GROUNDING CONDUCTOR TO SERVICE GROUNDING POINT(S). (REFER TO DETAIL ON DRAWING **E0-02**). INCLUDE (2) DOUBLE DUPLEX RECEPTACLES INSTALLED AT THIS TERMINAL BOARD SERVED FROM (2) 20A-120V-1Ø DEDICATED CIRCUITS. REFER TO COMMUNICATION RISER DIAGRAM ON DRAWING **E0-02** FOR ADDITIONAL INFORMATION.
 - ROUTE BRANCH CIRCUITING FOR RECEPTACLES AT THIS LOCATION VERTICALLY AT EACH FLOOR. PROVIDE HOMERUN AS SHOWN ON FOURTH FLOOR.

Seal

NOT FOR CONSTRUCTION

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC

whs engineering
2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**

3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title
**FIRST FLOOR POWER
PLAN**

Date: 03.05.2026	Project Number: 24-065
Drawn By: DJS	Drawing Number:
Checked By: KDS	
Approved: GSS	

E2.01A



- EXACT LOCATION OF MECHANICAL, PLUMBING, CHILLER, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT, ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THE MECHANICAL, PLUMBING, AND/OR ARCHITECTURAL DRAWINGS. COORDINATE EXACT LOCATIONS WITH RESPECTIVE CONTRACTORS AND/OR VENDOR PRIOR TO ANY ROUGH-IN.
- PRIOR TO ROUGH-IN, REVIEW AND COORDINATE WITH ALL OTHER TRADES' CONTRACT DOCUMENTS TO DETERMINE SPECIFIC MOUNTING LOCATIONS AND ELECTRICAL REQUIREMENTS (VOLTAGE, PHASE, KW, HP, CONNECTION TYPE, ETC.). FOR HVAC AND PLUMBING EQUIPMENT, COORDINATE EXACT MOUNTING LOCATIONS WITH THE SPECIFIC TRADE AND ARCHITECT.
- REFER TO WIRING SCHEDULE ON SHEET **FE03A/B/C** FOR 15A/20A RECEPTACLE BRANCH CIRCUITS FOR ALL CONDUCTOR SIZES TO ACCOUNT FOR VOLTAGE DROP
- ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN CONDUITS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
- A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

Seal

**NOT FOR
CONSTRUCTION**

Issue: _____ Date: _____ By: _____

SCHEMATIC DESIGN	01.07.26	BAC
------------------	----------	-----

DESIGN DEVELOPMENT	03.05.26	BAC
--------------------	----------	-----

CODED NOTES

- 1 LOCATION OF AREA OF RESCUE COMMUNICATION BASE STATION. REFER TO DIAGRAM ON DRAWING #E0-02.
- 2 REFER TO ELEVATOR GENERAL INSTALLATION NOTES ON DRAWING #E0-03 FOR ALL ELEVATOR ROOM AND ELEVATOR PIT ELECTRICAL REQUIREMENTS.
- 3 PROVIDE A 4' x 4' x 3/4" THICK PLYWOOD BACKBOARD PAINTED WITH FIRE RETARDANT PAINT FOR MAIN COMMUNICATION TERMINAL BOARD (TELEPHONE, TELEVISION, ETC.). INCLUDE ALL WORK REQUIRED BY RESPECTIVE UTILITIES. PROVIDE A COPPER GROUNDING BUS AND #6 AWG GROUNDING CONDUCTOR TO SERVICE GROUNDING POINT(S) (REFER TO DETAIL ON DRAWING #E0-02). INCLUDE (2) DOUBLE DUPLEX TELEPHONE INSTALLATIONS TO BE SERVED FROM 208-120V-1P2W DEDICATED CIRCUITS. REFER TO COMMUNICATION RISER DIAGRAM ON DRAWING #E0-02 FOR ADDITIONAL INFORMATION.
- 4 ROUTE BRANCH CIRCUITS FOR RECEPTACLES AT THIS LOCATION VERTICALLY AT EACH FLOOR. PROVIDE HOMERUN AS SHOWN ON FOURTH FLOOR.



2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**

**3455 W. Dublin Granville Rd,
Columbus OH, 43235**

Drawing Title

SECOND FLOOR POWER PLAN

Date	Project Number
03.05.2026	24-065

24-065

Drawn by

Drawing Number

DJS

50

KDS

E2.

E2.02A



- EXACT LOCATION OF MECHANICAL, PLUMBING, ELECTRICAL, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT, ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THE MECHANICAL, PLUMBING, AND/OR ARCHITECTURAL DRAWINGS. PROVIDE EXACT LOCATION WITH RESPECTIVE CONTRACTORS AND/OR VENDORS. PRIOR TO ANY ROUGH-IN'S.
- PRIOR TO ROUGH-IN, REVIEW AND COORDINATE WITH ALL OTHER TRADES' CONTRACT DOCUMENTS TO DETERMINE SPECIFIC MOUNTING LOCATIONS AND ELECTRICAL REQUIREMENTS (VOLTAGE, PHASE, KW, HP, CONNECTION TYPE, ETC.) FOR HVAC AND PLUMBING EQUIPMENT. COORDINATE EXACT MOUNTING LOCATIONS WITH THE SPECIFIC TRADE AND ARCHITECT.
- REFER TO WIRING SCHEDULE ON SHEET **FE03A/B/C** FOR 15A/20A RECEPTACLE BRANCH CIRCUITS FOR ALL CONDUCTOR SIZES TO ACCORD TO VOLTAGE(DROP)
- ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN A DESIGNATED JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
- A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR EACH PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

**NOT FOR
CONSTRUCTION**

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC

- 1 LOCATION OF AREA OF RESCUE COMMUNICATION BASE STATION. REFER TO DIAGRAM ON DRAWING #E0-02.
- 2 REFER TO ELEVATOR GENERAL INSTALLATION NOTES ON DRAWING #E-03 FOR ALL ELEVATOR ROOM AND ELEVATOR PIT ELECTRICAL REQUIREMENTS.
- 3 PROVIDE A 4' x 4' x 3/4" THICK PLYWOOD BACKBOARD PAINTED WITH FIRE RETARDANT PAINT FOR MAIN COMMUNICATION TERMINAL BOARD (TELEPHONE, TELEVISION, ETC.). INCLUDE ALL WORK REQUIRED BY RESPECTIVE UTILITIES. PROVIDE A COPPER GROUNDING BUS AND #6 AWG GROUNDING CONDUCTOR TO SERVICE GROUNDING POINT(S) (REFER TO DETAIL ON DRAWING #E-02) INCLUDE (2) DOUBLE DUPLEX TELEPHONE INSTALLED IN EACH ELEVATOR ROOM SERVICE BUS. SHOW 20' x 24" x 120" 14' BENDED CIRCUITS. REFER TO COMMUNICATION RISER DIAGRAM ON DRAWING #E-02 FOR ADDITIONAL INFORMATION.
- 4 ROUTE BRANCH CIRCUITING FOR RECEPTACLES AT THIS LOCATION VERTICALLY AT EACH FLOOR. PROVIDE HOMERUN AS SHOWN ON FOURTH FLOOR.



2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**

**3455 W. Dublin Granville Rd,
Columbus OH, 43235**

Drawing Title

**THIRD FLOOR POWER
PLAN**

Date	Project Number
------	----------------


03.05.2026	24-065
------------	--------

Drawn by

DJS

KDS

E2.03A



- GENERAL POWER AND COMMUNICATION PLAN NOTES
- EXACT LOCATION OF MECHANICAL, PLUMBING, KITCHEN, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT, ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THE MECHANICAL, PLUMBING, AND/OR ARCHITECTURAL DRAWINGS. COORDINATE EXACT LOCATIONS WITH RESPECTIVE CONTRACTORS AND/OR VENDORS PRIOR TO ANY ROUGH-INS.
 - PRIOR TO ROUGH-IN, REVIEW AND COORDINATE WITH ALL OTHER TRADES' CONTRACT DOCUMENTS TO DETERMINE SPECIFIC MOUNTING LOCATIONS AND ELECTRICAL REQUIREMENTS (VOLTAGE, PHASE, KW, HP, CONNECTION TYPE, ETC.) FOR HVAC AND PLUMBING EQUIPMENT. COORDINATE EXACT MOUNTING LOCATIONS WITH THE SPECIFIC TRADE AND ARCHITECT.
 - REFER TO WIRING SCHEDULE ON SHEET #E0.03A/B/C FOR 15A/20A RECEPTACLE BRANCH CIRCUITS FOR ALL CONDUCTOR SIZES TO ACCOUNT FOR VOLTAGE DROP.
 - ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN ALL CABINETS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
 - A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

CODED NOTES

- LOCATION OF AREA OF RESCUE COMMUNICATION BASE STATION. REFER TO DIAGRAM ON DRAWING #E0-02.
- REFER TO ELEVATOR GENERAL INSTALLATION NOTES ON DRAWING #E0-03 FOR ALL ELEVATOR ROOM AND ELEVATOR PIT ELECTRICAL REQUIREMENTS.
- PROVIDE A 4' x 4' x 3/4" THICK PLYWOOD BACKBOARD PAINTED WITH FIRE RETARDANT PAINT FOR MAIN COMMUNICATION TERMINAL BOARD (TELEPHONE, TELEVISION, ETC.). INCLUDE ALL WORK REQUIRED BY RESPECTIVE UTILITIES. PROVIDE A COPPER GROUNDING BUS AND #6 AWG GROUNDING CONDUCTOR TO SERVICE GROUNDING POINT(S). (REFER TO DETAIL ON DRAWING #E0-02). INCLUDE (2) DOUBLE DUPLEX RECEPTACLES INSTALLED AT THIS TERMINAL BOARD SERVED FROM (2) 20A-120V-1Ø DEDICATED CIRCUITS. REFER TO COMMUNICATION RISER DIAGRAM ON DRAWING #E0-02 FOR ADDITIONAL INFORMATION.
- ROUTE BRANCH CIRCUITING FOR RECEPTACLES AT THIS LOCATION VERTICALLY AT EACH FLOOR. PROVIDE HOMERUN AS SHOWN ON FOURTH FLOOR.

1
E2.04A
BUILDING A
FOURTH FLOOR POWER PLAN
SCALE: 3/32" = 1'-0"

Seal

NOT FOR
CONSTRUCTION

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC

whs
engineering
2012 West 25th Street, Suite 900
Cleveland, OH 44113
Phone: 216 227 8505


**OSU
AIRPORT WEST
BUILDING A**

3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title
**FOURTH FLOOR POWER
PLAN**

Date:	Project Number:
03.05.2026	24-065
Drawn By:	Drawing Number:
DJS	
Checked by:	
KDS	
Approved:	
GSS	

E2.04A



10 1

- EXACT LOCATION OF MECHANICAL, PLUMBING, KITCHEN, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT, ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THE MECHANICAL, PLUMBING, AND/OR ARCHITECTURAL DRAWINGS. COORDINATE EXACT LOCATIONS WITH RESPECTIVE CONTRACTORS AND/OR VENDORS PRIOR TO ANY ROUGH-INS.
- PRIOR TO ROUGH-IN, REVIEW AND COORDINATE WITH ALL OTHER TRADES' CONTRACT DOCUMENTS TO DETERMINE SPECIFIC MOUNTING LOCATIONS AND ELECTRICAL REQUIREMENTS (VOLTAGE, PHASE, KW, HP, CONNECTION TYPE, ETC.) FOR HVAC AND PLUMBING EQUIPMENT. COORDINATE EXACT MOUNTING LOCATIONS WITH THE SPECIFIC TRADE AND ARCHITECT.
- REFER TO WIRING SCHEDULE ON SHEET **FE-03A/B/C** FOR 15A/20A RECEPTACLE BRANCH CIRCUITS FOR ALL CONDUCTOR SIZES TO ACCOUNT FOR VOLTAGE DROP.
- ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN ALL CABINETS, JUNCTION BOXES, WIRING TROUSERS, ENCLOSURES, SPICE OR TERMINATION POINTS, ETC.

A NEW TYPE PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELBOARDS OR LOCATED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

① DWELLING UNIT HEAT PUMPS TO BE POWERED FROM RESPECTIVE TENANT PANEL. REFER TO TYPICAL DWELLING UNIT APPLIANCE CONNECTION SCHEDULE ON SHEET #E3-00 FOR LOAD INFORMATION, CIRCUIT BREAKER, DISCONNECT, AND CONDUCTOR SIZING.

**NOT FOR
CONSTRUCTION**

[illegible][illegible]

1

whs
engineering

2012 West 25th Street, Suite 90
Cleveland, OH 44113
Phone: 216 227 8505

3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title

**ROOF LEVEL POWER
PLAN**

Date	Project Number
03.05.2026	24-065
Drawn by	Drawing Number
DJS	
Checked by	
KDS	E2.05A
Approved	
GSS	

E2.05A

GENERAL "DWELLING UNIT" ELECTRICAL CONSTRUCTION NOTES

- A. EQUIPMENT AND MATERIALS USED ON THIS PROJECT SHALL BE NEW AND U.L. LABELED FOR THE APPLICATION.
- B. WORK SHALL BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE PROVISIONS OF LOCAL AND STATE CODES AS WELL AS THE CURRENT EDITION OF THE NATIONAL ELECTRICAL CODE (NEC), AS INTERPRETED BY THE LOCAL AUTHORITY HAVING JURISDICTION.
- C. MATERIAL OR LABOR WHICH IS NOT INDICATED ON THE DRAWINGS OR SPECIFICATION BUT WHICH IS OBVIOUSLY NECESSARY TO COMPLETE THE WORK SHALL BE PROVIDED. DRAWINGS OR MATERIALS ARE REQUIRED BECAUSE OF IGNORANCE OF THESE CONDITIONS.
- D. VISIT THE SITE OF THE WORK AND BECOME FAMILIAR WITH CONDITIONS AFFECTING THE INSTALLATION. SUBMISSION OF A PROPOSAL SHALL PRESUPPOSE KNOWLEDGE OF SUCH CONDITIONS AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED WHERE EXTRA LABOR OR MATERIALS ARE REQUIRED BECAUSE OF IGNORANCE OF THESE CONDITIONS.
- E. WHERE LIGHT SWITCHES ARE SHOWN ADJACENT TO ONE ANOTHER, THEY SHALL BE GROUPED TOGETHER INTO A 2, 3, OR 4 GANG DEVICE BOX WITH COMMON COVERPLATE.
- F. BACK BOXES IN DEMISING WALLS SHALL NOT BE ROUGHED-IN BACK TO BACK IN THE SAME STUD SPACE. PROVIDE FIRE-STOPPING AS REQUIRED TO MAINTAIN FIRE RATING.
- G. ELECTRICAL BOXES, ELECTRICAL EQUIPMENT, ETC. MUST BE FIRESTOPPED UNDER THE FOLLOWING CONDITIONS: BOXES LARGER THAN 16 SQUARE INCHES, IF HORIZONTAL SPACING BETWEEN BOXES IS LESS THAN 24 INCHES. WHEN MULTIPLE BOXES ARE LOCATED IN ONE STUD CAVITY OR IF THE AGGREGATE OF ALL BOXES EXCEEDS 100 SQUARE INCHES PER 100 SQUARE FEET. REFER TO LISTED SYSTEM DETAILS AND APPLICABLE LOCAL BUILDING CODE REQUIREMENTS.
- H. WHERE ELECTRICAL EQUIPMENT, OUTLET BOXES, ETC. ARE INSTALLED IN A FIRE RATED ASSEMBLY AND AS REQUIRED UNDER THE PARAMETERS LISTED ABOVE, FIRE (PUTTY) PADS SHALL BE PROVIDED TO MAINTAIN THE INTEGRITY OF THE FIRE RATED ASSEMBLY.
- I. WHEN ELECTRICAL EQUIPMENT, OUTLET BOXES, ETC. ARE INSTALLED IN A STUD PARTITION WHERE ADJACENT ROOMS ARE SIMILAR, THE OUTLETS SHALL BE STAGGERED AND FIRE RATED (PUTTY) PADS SHALL ALSO BE INSTALLED.
- J. FIRE RATED (PUTTY) PADS SHALL BE 3M "FIRE BARRIER MOLDABLE PUTTY PADS MPP+", FIRE RATED PRODUCTS SPECIALTIES CORPORATION TYPE "FRPS" ENCLOSURES, OR APPROVED EQUAL PRIOR TO PLACING BASE BID PRICE.
- K. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE FIRE RATING OF ALL CEILINGS, STRUCTURES, ETC. IN COMPLIANCE WITH ALL STANDARDS. WHERE BACK BOXES ARE REQUIRED TO BE INSTALLED TO SERVE LIGHT FIXTURES IN FIRE RATED CEILINGS, FIRE (PUTTY) PADS SHALL BE PROVIDED.
- L. REFER TO ARCHITECTURAL ELEVATIONS FOR MOUNTING LOCATION AND HEIGHT OF ALL WIRING DEVICES.
- M. COORDINATE THE EXACT LOCATION OF ALL RECEPTACLES AT CABINET LOCATIONS WITH G.C. CUT AND PATCH AS DIRECTED BY THE G.C.
- N. ALL DEVICES SHALL BE RESIDENTIAL GRADE, 15/20 AMP DEVICES. RECEPTACLES SHALL BE TAMPER RESISTANT TYPE IN COMPLIANCE WITH N.E.C. #406.12.
- O. SMOKE DETECTORS MUST BE INSTALLED FREE OF DUST OR ANY OTHER CONTAMINATION. LOCATE A MINIMUM OF 3'-0" FROM ALL SUPPLY AIR DIFFUSERS. LOCATE A MINIMUM OF 1'-0" FROM ANY PART OF ANY LIGHTING FIXTURES. DO NOT LOCATE ABOVE PENDANT MOUNTED OR INDIRECT LIGHTING FIXTURES. DO NOT LOCATE ABOVE CEILING FANS.
- P. IN ALL SINGLE, OR, MULTI-FAMILY DWELLING UNITS, RECEPTACLES SHALL BE LOCATED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITION OF THE N.E.C. ELECTRICAL EQUIPMENT, DEVICES, ETC. SHALL BE INSTALLED AND SPACED AS DIRECTED BY THE N.E.C. WITH SPECIFIC ATTENTION TO ARTICLE #210.52(A) THROUGH #210.52(I).
- Q. ALL PENETRATIONS IN FIRE RATED FLOORS, SHAFTS AND WALLS SHALL BE FIRE STOPPED. THE INSTALLATION OF FIRE STOPPING MATERIALS SHALL CONFORM TO THE LATEST FIRE RESISTANCE DIRECTORY AS PUBLISHED BY U.L.
- U. ALL RECEPTACLES SERVING KITCHEN COUNTER TOP SURFACES SHALL BE G.F.C.I. PROTECTED IN ACCORDANCE WITH N.E.C. ARTICLE #210.8(A)(6).
- V. ALL RECEPTACLES SHALL LOCATED WITHIN 6'-0" OF THE OUTSIDE OF ALL SINKS, SHOWER STALLS, AND, BATH TUBS SHALL BE G.F.C.I. PROTECTED IN ACCORDANCE WITH N.E.C. ARTICLE #210.8(A)(7).
- W. WHERE G.F.C.I. DEVICES ARE INSTALLED TO SERVE LARGE APPLIANCES, OR, APPLIANCES BELOW COUNTERTOP SURFACES, THE G.F.C.I. DEVICE SHALL BE READILY ACCESSIBLE AS REQUIRED BY N.E.C. ARTICLE #422.5 AND AS DEFINED BY N.E.C. ARTICLE #100. PROVIDE G.F.C.I. TYPE CIRCUIT BREAKERS WHERE APPLICABLE. PROVIDE PROPER IDENTIFICATION AT RELATED DEVICE LOCATIONS INDICATING "G.F.C.I. PROTECTED".
- X. PROVIDE ARC-FAULT PROTECTION FOR APPLICABLE BRANCH CIRCUITS IN ACCORDANCE WITH N.E.C. ARTICLE #210.12(A).

TYPICAL UNIT APPLIANCE/EQUIPMENT CONNECTION SCHEDULE									
·	APPLIANCE/EQUIPMENT DESCRIPTION	VOLTAGE/ PHASE	KW	CONNECTION TYPE			WIRE/CONDUIT SIZE	NOTE	S
				NEMA TYPE	DISCONNECT/SWITCH	HEIGHT			
1	REFRIGERATOR	120V-1ø	0.600	5-20R	-	54"	2ø12, 1ø12(G), 3/4"C.	1	
2	ELECTRIC RANGE/OVEN	120/208V-1ø	8.000	14-50R	-	VERIFY	3ø6, 1ø10(G), 1"C.	1	
3A	RANGE HOOD (ADA UNITS)	120V-1ø	0.480		DIRECT	VERIFY	2ø12, 1ø12(G), 3/4"C.	1,4	
3B	RANGE HOOD/MICROWAVE	120V-1ø	1.680	5-20R	-	VERIFY	2ø12, 1ø12(G), 3/4"C.	1	
4	DISHWASHER	120V-1ø			-	SEE NOTE 2	2ø12, 1ø12(G), 3/4"C.	1,2	
5	DISPOSER	120V-1ø	1.200	5-20R	-				
6	WASHING MACHINE/LAUNDRY	120V-1ø	1.500	5-20R	-	42"	2ø12, 1ø12(G), 3/4"C.	1	
7	ELECTRIC DRYER	120/208V-1ø	5.000	14-30R	-	42"	3ø10, 1ø10(G), 3/4"C.	1	
8	ELECTRIC WATER HEATER	208V-1ø	4.500	-	30A-2P, NEMA 1	AT UNIT	2ø10, 1ø10(G), 3/4"C.	1,6	
9A	1.5 TON AIR HANDLER	208V-1ø	4.784	-	30A-2P, NEMA 1	AT UNIT	2ø10, 1ø10(G), 3/4"C.	1,6	
9B	2 TON AIR HANDLER	208V-1ø	5.824	-	30A-2P, NEMA 1	AT UNIT	2ø10, 1ø10(G), 3/4"C.	1,6	
9C	2.5 TON AIR HANDLER	208V-1ø	8.528	-	60A-2P, NEMA 1	AT UNIT	2ø6, 1ø10(G), 1"C.	1,6	
10A	1.5 TON ROOFTOP HEAT PUMP	208V-1ø	2.080	-	30A-2P, NEMA 3R	AT UNIT	2ø10, 1ø10(G), 3/4"C.	1,5	
10B	2 TON ROOFTOP HEAT PUMP	208V-1ø	2.704	-	30A-2P, NEMA 3R	AT UNIT	2ø10, 1ø10(G), 3/4"C.	1,5	
10C	2.5 TON ROOFTOP HEAT PUMP	208V-1ø	3.328	-	30A-2P, NEMA 3R	AT UNIT	2ø8, 1ø10(G), 3/4"C.	1,5	
11	EXHAUST FAN	120V-1ø	0.055	-	INTEGRAL	CEILING	2ø12, 1ø12(G), 3/4"C.	1,3	

APPLIANCE/EQUIPMENT CONNECTION SCHEDULE NOTES:

- VERIFY ALL EQUIPMENT SPECIFICATIONS (VOLTAGE, CONNECTION, ETC.) WITH OWNER AND/OR ARCHITECT PRIOR TO PLACING PURCHASE ORDER FOR DEVICES AND ROUGH-IN. VERIFY THE EXACT MOUNTING HEIGHT WITH ARCHITECTURAL ELEVATIONS, MILLWORK, ETC. PRIOR TO ROUGH-IN.
- PROVIDE A DUPLEX RECEPTACLE TO SERVE DISHWASHER AND DISPOSER PROTECTED BY AN UPSTREAM GFCI TYPE CIRCUIT BREAKER. COORDINATE LOCATION OF DEVICE IN MILLWORK WITH ARCHITECT/G.C. AT ISLAND LOCATIONS, INSTALL AN AIR PUSH BUTTON TYPE BUTTON (PROVIDED BY P.C.) FOR CONTROL OF DISHWASHER. INCLUDE ALL COSTS OF CORE DRILLING MILLWORK/SINK TO INSTALL PUSH BUTTON. ENSURE INSTALLED BUTTON ALLOWS FOR DISHWASHER TO BE SERVED BY THE SAME RECEPTACLE. AT NON-ISLAND KITCHEN COUNTER LOCATIONS, PROVIDE A SINGLE POLE SWITCH AT THE KITCHEN BACKSPLASH (FINAL LOCATION BY ARCHITECT). SPLIT-WIRE THE RECEPTACLE AND WIRE SUCH THE SWITCH ONLY CONTROLS THE TOP OUTLET. **ALL FINAL DEVICE LOCATIONS SHALL BE ADA COMPLIANT IN ADA COMPLIANT UNITS.**
- CONNECT TO INTEGRAL DISCONNECT SWITCH AND CONNECT TO APARTMENT UNIT LIGHTING CIRCUIT. VERIFY EXACT REQUIREMENTS WITH EQUIPMENT. WIRE SUCH THAT EXHAUST FAN RECEIVES CONSTANT LINE VOLTAGE POWER AHEAD OF ALL SWITCHING AND CONTROL. **REFER TO DETAIL ON THIS SHEET.**
- PROVIDE A REDUNDANT (3-WAY) SWITCH IN ADA UNITS FOR CONTROL OF RANGE HOOD. SWITCH SHALL BE LOCATED IN ADA-COMPLIANT LOCATION. MODIFY RANGE HOOD WIRING AS REQUIRED (REFER TO HOOD UNIT WIRING DIAGRAM) FOR ADDITIONAL CONTROL.
- BRANCH CIRCUITING SIZED TO ACCOUNT FOR VOLTAGE DROP.
- INSTALL DISCONNECT IN CLOSET SUCH THAT NEC #110.26 WORKING CLEARANCE IS MAINTAINED.

DWELLING UNIT LUMINAIRE SCHEDULE

TYPE	LAMP	WATTAGE	VOLTAGE	DIMMING TYPE	DESCRIPTION	CATALOG NUMBER	EQUIVALENT MANUFACTURER/REMARKS
M-1	-	-	120	-	LED MIRROR LIGHT USED IN BATHROOMS.	-	-
PL-1	-	-	120	-	LED PENDANT LIGHT USED THROUGHOUT THE UNITS.	-	-
PL-2	-	-	120	-	LED PENDANT USED OVER BATHROOM SHOWERS.	-	-
UC-1	-	-	120	-	LED UNDERCOUNTER LIGHT USED IN KITCHEN AREA.	-	-

LUMINAIRE SCHEDULE GENERAL NOTES:

- VERIFY ALL LUMINAIRE COLORS, TRIMS, LENGTHS, ETC. WITH THE **ARCHITECT/OWNER/DEVELOPER/DESIGNER** PRIOR TO PLACING FINAL PURCHASE ORDERS. SUBMISSION OF SHOP DRAWINGS WILL BE INTERPRETED AS HAVING BEEN COORDINATED WITH THE AFOREMENTIONED PARTIES.
- PROVIDE ALL LENGTHS, FEEDS, ACCESSORIES, CONNECTORS, WIRING, POWER SUPPLIES, DRIVERS, ETC. FOR A COMPLETE INSTALLATION. VERIFY THE COMPLETE BILL OF MATERIAL WITH MANUFACTURER'S REPRESENTATIVE AND ENSURE ALL EQUIPMENT IS INCLUDED IN BID PRICE. COORDINATE INSTALLATION WITH ARCHITECTURAL DETAILS.
- VERIFY FINAL LUMINAIRE LOCATIONS WITH OTHER CEILING MOUNTED EQUIPMENT SUCH AS DIFFUSERS, FIRE ALARM DEVICES, SPEAKERS, ETC., WITH ARCHITECTURAL REFLECTED CEILING PLANS.
- VERIFY EXACT MOUNTING HEIGHT AND LOCATIONS OF ALL WALL MOUNTED AND PENDANT MOUNTED LUMINAIRES WITH ARCHITECTURAL PLANS AND ELEVATIONS PRIOR TO ROUGH-IN.
- ANY PROPOSED ALTERNATE LUMINAIRES SHALL BE APPROVED BY THE **ARCHITECT/OWNER/DEVELOPER/DESIGNER** PRIOR TO FINAL BID PRICING.
- SHOULD THE CONTRACTOR PROPOSE TO FURNISH MATERIALS, EQUIPMENT, AND DEVICES, OTHER THAN THOSE SPECIFIED AND LISTED, THE CONTRACTOR SHALL SUBMIT A WRITTEN REQUEST FOR SUBSTITUTIONS, TO THE ENGINEER AT LEAST TEN (10) BUSINESS DAYS PRIOR TO BID OPENING. THE REQUEST SHALL BE AN ALTERNATE TO THE ORIGINAL BID AND SHALL INCLUDE A COMPLETE SPECIFICATIONS CUT SHEET SUBMITTAL AS OUTLINED IN THE SPECIFICATIONS, COMPLETE WITH DESCRIPTIVE (MANUFACTURER, BRAND NAME, CATALOG NUMBER, ETC.) AND TECHNICAL DATA FOR ALL ITEMS. INDICATE ANY ADDITIONS OR DEDUCTIONS TO THE CONTRACT PRICE WITH THE SUBSTITUTION SUBMITTAL AND ON THE BID FORM.
- ANY FINAL SELECTED/INSTALLED LIGHT FIXTURES WITHOUT A SPECIFICATION (OR TO BE SPECIFIED LATER BY **ARCHITECT/OWNER/DEVELOPER/DESIGNER**) LISTED IN THIS SCHEDULE SHALL NOT EXCEED THE WATTAGE LISTED, SHALL NOT HAVE A LOWERED DELIVERED LUMENS (IF LISTED), AND SHALL MATCH THE COLOR TEMPERATURE (IF LISTED).

TYPICAL 1 BED & 2 BED DWELLING UNIT ELECTRIC SERVICE CALC.				
DESCRIPTION	AREA	LOAD	TOTAL WC	N.E.C. ARTICLE
RECEPTACLES/LIGHTINGS	1200	3	3600	220.82(B)(1)
SMALL APPLIANCE CIRCUITS (2 x 1500)	-	3000	3600	220.82(B)(2)
LAUNDRY CIRCUIT (WASHING MACHINE)	-	1500	1500	220.82(B)(2)
REFRIGERATOR	-	600	600	220.82(B)(3)
ELECTRIC RANGE/OVEN	-	8000	8000	220.82(B)(3)
RANGE HOOD/MICROWAVE	-	1680	1680	220.82(B)(3)
DISHWASHER/DISPOSER	-	1200	1200	220.82(B)(3)
ELECTRIC DRYER	-	5000	5000	220.82(B)(3)
ELECTRIC WATER HEATER	-	4500	4500	220.82(B)(3)
TOTAL CONNECTED GENERAL LOAD	-	-	29080	-
100% OF FIRST 10KW + 40% OF REMAINING	-	-	17632	220.82(B)
INTERIOR AIR HANDLER	-	5824	5824	-
ROOFTOP HEAT PUMP	-	2704	2704	-
TOTAL CONNECTED HVAC LOAD	-	-	8528	-
65% OF AIR HAND(S). + 100% OF HEAT PUMP(S)	-	-	6490	220.82(C)(3)
TOTAL DEMAND LOAD	-	-	24,122 W	-
AMPS AT 120/208V-1Ø-3W			116.0 A	

TYPICAL 3 BED DWELLING UNIT ELECTRIC SERVICE CALC.				
DESCRIPTION	AREA	LOAD	TOTAL WC	N.E.C. ARTICLE
RECEPTACLES/LIGHTINGS	1450	3	4350	220.82(B)(1)
SMALL APPLIANCE CIRCUITS (2 x 1500)	-	3000	3000	220.82(B)(2)
LAUNDRY CIRCUIT (WASHING MACHINE)	-	1500	1500	220.82(B)(2)
REFRIGERATOR	-	600	600	220.82(B)(3)
ELECTRIC RANGE/OVEN	-	8000	8000	220.82(B)(3)
RANGE HOOD/MICROWAVE	-	1680	1680	220.82(B)(3)
DISHWASHER/DISPOSER	-	1200	1200	220.82(B)(3)
ELECTRIC DRYER	-	5000	5000	220.82(B)(3)
ELECTRIC WATER HEATER	-	4500	4500	220.82(B)(3)
TOTAL CONNECTED GENERAL LOAD	-	-	29630	-
100% OF FIRST 10KW + 40% OF REMAINING	-	-	17932	220.82(B)
INTERIOR AIR HANDLER	-	8528	8528	-
ROOFTOP HEAT PUMP	-	3328	3328	-
TOTAL CONNECTED HVAC LOAD	-	-	11856	-
65% OF AIR HAND(S). + 100% OF HEAT PUMP(S)	-	-	8871	220.82(C)(3)
TOTAL DEMAND LOAD	-	-	26,803 W	-
AMPS AT 120/208V-1Ø-3W			128.9 A	

TYPICAL DWELLING UNIT PANEL SCHEDULE									
NAME: TP1				VOLTAGE: 120/208-1Ø-3W					
MINIMUM KAIC: 10				TYPE: FLUSH MOUNTED					
MCR: 125A MLO				KWD: SEE ADJACENT CALC.					
CKT	DESCRIPTION	C/B	Ø	C/B	DESCRIPTION	CKT			
A/G	1 SMALL APPLIANCE REC.	20/1	A	20/1	REFRIGERATOR	2	A	G	
A/G	3 SMALL APPLIANCE REC.	20/1	B			4			
A	5 LIVING REC.	20/1	A	50/2	ELECTRIC RANGE	6		G2	
G	7 BATHROOM REC.	20/1	B	20/1	RANGE HOOD/MICRO.	8	A	G	
A	9 LIGHTING/S.D.	20/1	A	20/1	DISHWASHER/DISPOSER	10	A	G	
A	11 BEDROOM REC.	20/1	B	20/1	WASHING MACHINE	12	A	G	
13	SPACE	-	A			14			
15	SPACE	-	B	30/2	ELECTRIC DRYER	16		G2	
17	SURGE PROTECTION	-	A	30/2	ELECTRIC WATER HEATER	18			
19			B			20			
21	AIR HANDLER	25/2	A	15/2	ROOFTOP HEAT PUMP	22			
23			B			24			

TYPICAL DWELLING UNIT PANEL SCHEDULE NOTES:

Δ: PROVIDE AN ARC-FAULT CIRCUIT INTERRUPTER (AFCI) TYPE CIRCUIT BREAKER FOR THIS BRANCH CIRCUIT.

Ω: PROVIDE GROUND-FAULT CIRCUIT INTERRUPTER (GFCI) PROTECTION FOR THIS BRANCH CIRCUIT. PROVIDE A GFCI-TYPE CIRCUIT BREAKER IF GFCI-TYPE RECEPTABLES/DEVICES ARE NOT PROVIDED DOWNSTREAM ON THIS BRANCH CIRCUIT.

Ω2: PROVIDE A GROUND-FAULT CIRCUIT INTERRUPTER (GFCI) TYPE CIRCUIT BREAKER FOR THIS BRANCH CIRCUIT.

TYPICAL DWELLING UNIT PANEL SCHEDULE									
NAME: TP2				VOLTAGE: 120/208-1Ø-3W					
MINIMUM KAIC: 10				TYPE: FLUSH MOUNTED					
MCR: 125A MLO				KWD: SEE ADJACENT CALC.					
CKT	DESCRIPTION	C/B	Ø	C/B	DESCRIPTION		CKT		
A/G	1 SMALL APPLIANCE REC.	20/1	A	20/1	REFRIGERATOR	2	A/G		
A/G	3 SMALL APPLIANCE REC.	20/1	B						
A	5 LIVING REC.	20/1	A	50/2	ELECTRIC RANGE	4	G2		
G	7 BATHROOM REC.	20/1	B	20/1	RANGE HOOD/MICRO.	8	A/G		
A	9 LIGHTING/S.D.	20/1	A	20/1	DISHWASHER/DISPOSER	10	A/G		
A	11 BEDROOM REC.	20/1	B	20/1	WASHING MACHINE	12	A/G		
A	13 BEDROOM REC.	20/1	A						
G	15 BATHROOM REC.	20/1	B	30/2	ELECTRIC DRYER	14	G2		
17	SURGE PROTECTION	-	A	30/2	ELECTRIC WATER HEATER	18			
19			B			20			
21	AIR HANDLER	30/2	A	20/2	ROOFTOP HEAT PUMP	22			
23			B			24			

TYPICAL DWELLING UNIT PANEL SCHEDULE NOTES:

Δ: PROVIDE AN ARC-FAULT CIRCUIT INTERRUPTER (AFCI) TYPE CIRCUIT BREAKER FOR THIS BRANCH CIRCUIT.

Ω: PROVIDE GROUND-FAULT CIRCUIT INTERRUPTER (GFCI) PROTECTION FOR THIS BRANCH CIRCUIT. PROVIDE A GFCI-TYPE CIRCUIT BREAKER IF GFCI-TYPE RECEPTACLES/DEVICES ARE NOT PROVIDED DOWNSTREAM ON THIS BRANCH CIRCUIT.

Ω2: PROVIDE A GROUND-FAULT CIRCUIT INTERRUPTER (GFCI) TYPE CIRCUIT BREAKER FOR THIS BRANCH CIRCUIT.








TYPICAL DWELLING UNIT PANEL SCHEDULE									
NAME: TP3				VOLTAGE: 120/208-1ø-3W					
MINIMUM KAIC: 10				TYPE: FLUSH MOUNTED					
MCR: 150A MLO				KWD: SEE ADJACENT CALC.					
CKT	DESCRIPTION	C/B	Ø	C/B	DESCRIPTION	CKT			
A/G	1 SMALL APPLIANCE REC.	20/1	A	20/1	REFRIGERATOR	2	A	G	
A/G	3 SMALL APPLIANCE REC.	20/1	B						
A	5 LIVING REC.	20/1	A	50/2	ELECTRIC RANGE	4	G2		
G	7 BATHROOM REC.	20/1	B	20/1	RANGE HOOD/MICRO.	8	A	G	
A	9 LIGHTING/S.D.	20/1	A	20/1	DISHWASHER/DISPOSER	10	A	G	
A	11 BEDROOM REC.	20/1	B	20/1	WASHING MACHINE	12	A	G	
A	13 BEDROOM REC.	20/1	A						
G	15 BATHROOM REC.	20/1	B	30/2	ELECTRIC DRYER	14		G2	
17	SURGE PROTECTION	-	A	30/2	ELECTRIC WATER HEATER	18			
19			B			20			
21	INTERIOR AIR HANDLER	45/2	A	25/2	ROOFTOP HEAT PUMP	22			
23			B			24			
A	25 BEDROOM REC.	20/1	A	-	SPACE	26			
27	SPACE	-	B	-	SPACE	28			

TYPICAL DWELLING UNIT PANEL SCHEDULE NOTES:

1. PROVIDE AN ARC-FAULT CIRCUIT INTERRUPTER (AFCI) TYPE CIRCUIT BREAKER FOR THIS BRANCH CIRCUIT.

2. PROVIDE GROUND-FAULT CIRCUIT INTERRUPTER (GFCI) PROTECTION FOR THIS BRANCH CIRCUIT. PROVIDE A GFCI-TYPE CIRCUIT BREAKER IF GFCI-TYPE RECEPTILES/DEVICES ARE NOT PROVIDED DOWNSTREAM ON THIS BRANCH CIRCUIT.

3. PROVIDE A GROUND-FAULT CIRCUIT INTERRUPTER (GFCI) TYPE CIRCUIT BREAKER FOR THIS BRANCH CIRCUIT.



- GENERAL DWELLING UNIT ELECTRICAL PLAN NOTES
- ALL LIGHT FIXTURES, CEILING FANS, AND BATHROOM/KITCHEN EXHAUST FANS SHALL BE CONNECTED TO CIRCUIT #9 IN RESPECTIVE UNIT LOAD CENTER UNLESS SHOWN OTHERWISE.
 - REFER TO SHEET #E3-00 FOR ALL UNIT DETAILS, INCLUDING APPLIANCE SCHEDULES.
 - FLOOR RECEPTABLES MAY BE INSTALLED IN LIEU OF WALL RECEPTABLES SHOULD WINDOWS/GLAZING OR SLIDING DOOR RECESSED GLASS INTERFERE WITH WALL MOUNTING OF ANY TYPE WITHIN THE DWELLING UNIT. FLOOR RECEPTABLES SHALL BE INSTALLED WITHIN 18" OF WINDOWS/WALLS OR PER NEC #210.52(A)(3).

- ## CODED NOTES
- ① LOCATION OF NEW TENANT CIRCUIT BREAKER LOAD CENTER, REFER TO TYPICAL UNIT CIRCUIT BREAKER PANEL, SCHEDULE ON SHEET **FE3-00** FOR ADDITIONAL INFORMATION. PROVIDE AREA BRANCH CIRCUITS SHALL BE PROVIDED WITH ARC-FAULT CIRCUIT INTERRUPTER PROTECTION IN ACCORDANCE WITH N.E.C. ARTICLE #210.12(A).
 - ② THIS FIRE ALARM DEVICE SHALL BE CONNECTED TO THE BASE BUILDING FIRE ALARM SYSTEM. VERIFY FINAL DRAWING WITH A.H.J. AND FIRE MARSHAL.
 - ③ LOCATION OF STRUCTURED MEDIA ENCLOSURE "SME", REFER TO DETAIL ON DRAWING **FE3-00** FOR ADDITIONAL INFORMATION. PROVIDE POWER FROM NEAREST LIVING AREA BRANCH CIRCUIT.
 - ④ COORDINATE FINAL LOCATION OF JUNCTION BOX FOR FUTURE KITCHEN COUNTER RECEPTACLE WITH G.C. AND OWNERSHIP. ROUTE AN EMPTY "X" WITH PULLWIRE TO THE JUNCTION BOX. SHALL APPLY TO ALL KITCHEN COUNTERS. VERIFY THE FINAL INSTALLATION SHALL BE IN COMPLIANCE WITH NEC SECTION 210.52(C)(3).

See

**NOT FOR
CONSTRUCTION**

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BA
DESIGN DEVELOPMENT	03.05.26	BA

whs
engineering

2012 West 25th Street, Suite 90
Cleveland, OH 44113
Phone: 216 227 8505

**OSU
AIRPORT WEST
BUILDING A**

3455 W. Dublin Granville Rd,
Columbus OH, 43235

Drawing Title

**TYPICAL DWELLING UNIT
ELECTRICAL PLANS**

Date	Project Number
------	----------------



Project Number	
----------------	--


03.0

24-065

10

DJS






- ALL LIGHT FIXTURES, CEILING FANS, AND BATHROOM/KITCHEN EXHAUST FANS SHALL BE CONNECTED TO CIRCUIT #9 IN RESPECTIVE UNIT LOAD CENTER UNLESS SHOWN OTHERWISE.
- REFER TO SHEET #E3-00 FOR ALL UNIT DETAILS, INCLUDING APPLIANCE SCHEDULES.
- FLOOR RECEPTABLES MAY BE INSTALLED IN LIEU OF WALL RECEPTABLES SHOULD WINDOWS/GLAZING OR SLIDING DOOR RECESSED POCKETS INTERFERE WITH WALL MOUNTING AT ANY LOCATION WITHIN THE DWELLING UNIT. FLOOR RECEPTABLES SHALL BE INSTALLED WITHIN 18" OF WINDOWS/WALLS OR PER NEC #210.52(A)(3).

- ① LOCATION OF NEW TENANT CIRCUIT BREAKER LOAD CENTER, REFER TO TYPICAL UNIT CIRCUIT BREAKER PANEL SCHEDULE ON SHEET **f3-30** FOR ADDITIONAL INFORMATION. ALL LIVING AREA BRANCH CIRCUITS SHALL BE PROVIDED WITH ARC-FAULT CIRCUIT INTERRUPTER PROTECTION. PROVIDE PROTECTIVE DEVICES TO MEET ALL CODES.
- ② THIS FIRE ALARM DEVICE SHALL BE CONNECTED TO THE BASE BUILDING FIRE ALARM SYSTEM. VERIFY FINAL LOCATION WITH A.J.D. AND FIRE MARSHAL.
- ③ LOCATION OF STRUCTURED MEDIA ENCLOSURE "SME", REFER TO DETAIL ON DRAWING **f3-30** FOR ADDITIONAL INFORMATION. PROVIDE POWER FROM NEAREST LIVING AREA BRANCH CIRCUIT.
- ④ COORDINATE FINAL LOCATION OF JUNCTION BOX FOR FUTURE KITCHEN COUNTER RECEPTACLE WITH G.C. AND OWNERSHIP. ROUTE AN EMPTY 1" TUB WITH PULLWIRE TO THE SMALL APPL. AREA. PROVIDE A 1/2" DIA. HOLE THROUGH THE WALL FOR THE FINAL INSTALLATION SHALL BE IN COMPLIANCE WITH SECTION 22.02(C)(3)(C).

Issue:	Date:	By:
SCHEMATIC DESIGN	01.07.26	BAC
DESIGN DEVELOPMENT	03.05.26	BAC



**OSU
AIRPORT WEST
BUILDING A**

**3455 W. Dublin Granville Rd,
Columbus OH, 43235**

Drawing Title

**TYPICAL DWELLING UNIT
ELECTRICAL PLANS**

Date 03.05.2026	Project Number 24-065
Drawn by DJS	Drawing Number E3.03A
Checked by KDS	
Approved GSS	